LOCATION MAP



SCALE: 1"=1000'

I CERTIFY THAT I HAVE BEEN IN RESPONSIBLE CHARGE OF THE DESIGN OF THIS PROJECT IN ACCORDANCE WITH THE RULES OF THE GEORGIA STATE BOARD OF REGISTRATION FOR PROFESSIONAL ENGINEERS AND LAND SURVEYORS. I FURTHER CERTIFY, TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THESE PLANS AND SPECIFICATIONS WILL ACCURATELY REFLECT THE DESIGN DEVELOPMENT REPORT (DDR) PREVIOUSLY REVIEWED AND CONCURRED WITH BY EPD. I FURTHER CERTIFY THAT THE SYSTEM AS DESIGNED CAN REASONABLY BE EXPECTED TO CONSISTENTLY MEET ALL CURRENTLY APPLICABLE PERMIT LIMITS, CONDITIONS, AND REGULATORY REQUIREMENTS, PROVIDED THE FACILITY IS CONSTRUCTED AS DESIGNED AND PROPERLY OPERATED AND MAINTAINED.

APRIL 11, 2024

THE CITY OF SYLVANIA 624 FRIENDSHIP ROAD, SYLVANIA, GA 30467

PREPARED FOR



VICINITY MAP

CONSTRUCTION PLANS FOR SYLVANIA WPCP UPGRADES

LOCATED IN

SCREVEN COUNTY, GEORGIA

SYLVANIA WPCP TREATMENT PLANT UPGRADES						
DA	DATE: 4/11/2024 PROJECT #: 1521.2201					
7.						
6.						
5.						
4.						
3.						
2.						
1.	ISSUED FOR BID	4/12/24	DLO			
Rev.	Description	Date	Apr.			



1039 SULLIVAN ROAD, SUITE 200, NEWNAN, GEORGIA 30265 (P) 678.552.2106 | (F) 678.552.2107 COA NO. PEF000625 | EXP. 06/30/2024









SHEET #	DWG. #	DRAWING TITLE
GENERAL		
1	G100	COVER
2	G101	SHEET INDEX
3	G102	GENERAL NOTES
CIVIL		
4	C100	EXISTING CONDITIONS OVERALL
5	C101	EXISTING CONDITIONS SECTION 1
6	C102	EXISTING CONDITIONS SECTION 2
7	C103	EXISTING CONDITIONS SECTION 3 DEMOLITION PLAN SECTION 1
9	C111	DEMOLITION PLAN SECTION 2
10	C112	DEMOLITION PLAN SECTION 3
11	C200	OVERALL PROPOSED SITE PLAN
12	C201	PROPOSED SITE PLAN SECTION 1
13	C202	PROPOSED SITE PLAN SECTION 2
14	C300	OVERALL PROPOSED PIPING PLAN
16	C301	PROPOSED PIPING PLAN SECTION 1
17	C302	PROPOSED PIPING PLAN ECTION 2
18	C303	PROPOSED PIPING PLAN SECTION 3
19	C304	
20 21	C305	HYDRAULIC PROFILES
22	C500	ESPC COVER
23	C501	ESPC NOTES
24	C502	ESPC CHECKLIST
25	C503	
26	C510	ERUSION CONTROL PLAN - ALL PHASES
27	C600	ESPC DETAILS
29	C700	WATER & SEWER DETAILS
30	C701	SEWER DETAILS
31	C702	MISCELLANEOUS CIVIL DETAILS
MECHANICAL		
32	M100	STAGED REACTOR MECHANICAL PLANS
33	M101	STAGED REACTOR MECHANICAL SECTIONS
34	M102	STAGE REACTOR MECHANICAL PLANS
36	M103	PROPOSED CLARIFIER PIPING MODIFICATIONS
37	M105	SLUDGE COLLECTION BOX SECTIONS & DETAILS
38	M106	DISC FILTER MECHANICAL PLAN
39	M107	DISC FILTER MECHANICAL PLAN
40	M108	PARSHALL FLUME/CHLORINE CONTACT CHAMBER/CASCADE AERATION
41	M109	AS FOMP STATION FLAN & SECTION AEROBIC DIGESTER MECHANICAL PLAN & SECTIONS
43	M111	AEROBIC DIGESTER SECTIONS & DETAILS
44	M112	DEWATERING BUILDING EXISTING CONDITIONS & DEMO PLAN
45	M113	DEWATERING BUILDING EQUIPMENT LAYOUT
46	M114	DEWATERING PROCESS SKID PIPING LAYOUT
47	M116	CHEMICAL FEED PLAN & SECTIONS CHEMICAL FEED SECTIONS
49	M200	PROCESS PIPING DETAILS
50	M201	HANDRAIL & LADDER DETAILS
51	M202	GRATING & HATCH DETAILS
52	M203	MISCELLANEOUS MECHANICAL DETAILS
STRUCTURAL		
53	S100	STAGED REACTOR STRUCTURAL PLAN
55	S101 S102	PARSHALL FLUME/CHLORINE CONTACT CAHMBER/CASCADE AERATION STRUCTURAL PLANS & SECTIONS
56	S103	PARSHALL FLUME STRUCTURAL PLANS & SECTIONS
57	S104	CASCADE AERATION STRUCTURAL PLANS & SECTIONS
58	S105	DIGESTOR STRUCTURAL
59	S106	
	5200	STRUCTURAL DETAILS
	E 404	
62	E101 E102	ELECTRICAL NOTES & LEGEND
63	E102	OVERALL ELECTRICAL SITE PLAN
64	E104	ENLARGED SITE PLAN
65	E105	STAGED REACTOR ELECTRICAL PLAN
66	E106	DISC FILTER ELECTRICAL PLAN
67	E107	
69	E108	AEROBIC DIGESTOR ELECTRICAL PLAN
70	E110	DEWATERING BUILDING ELECTRICAL PLAN
71	E111	CHEMICAL FEED ELECTRICAL PLAN
72	E112	AQUAPASS SCHEMATIC
73	E113	ELECTRIC DETAILS 1
74	E114	ELECTRIC DETAILS 2

Science &			1039 SULLIVAN ROAD, SUITE 200, NEWNAN, GEORGIA 30265	(P) 678.552.2106 (F) 678.552.2107 COA No. PEF000625 EXP. 06/30/2024
C L QEGIS	C G TERE	いいいませんど		*
			4/12/24	Date Apr.
			ISSUED FOR BID	. Description
Date:Drawn by:Check by:84/11/24MGWDLO7Project #:Design by:Review by:61521.2201DLODLO5	F	2	1	Rev
FOR FOR	SYLVANIA WPCP UPGRADES			LOCATED IN SCREVEN COUNTY, GEORGIA
	SHEET INDEA			
DRAWIN G	√G ()	N 1	0.	

(GENERAL NOTES:		STR	UCTURAL NOTES
	1. OWNER/ DEVELOPER:	CITY OF SYLVANIA ADDRESS: 104 SOUTH MAIN STREET, SYLVANIA, GA 30467 CONTACT: STACY MATHIS, CITY MANAGER, (912) 564-7411	1.	THE CONTRACTOR SHALL COORDINATE STRUC INCLUDES LOCATING THICKENED SLABS, DRAIN CONDUIT, AND ETC. BEFORE CONSTRUCTION B
:	2. ENGINEER/SURVEYOR:	INTEGRATED SCIENCE & ENGINEERING 1039 SULLIVAN ROAD, SUITE 200 NEWNAN, GA 30265 CONTACT: DAVIS OZIER, P.E. (678) 552-2106	2.	THE STRUCTURES HAVE BEEN DESIGNED FOR CONSTRUCTION ARE THE SOLE RESPONSIBILIT SHALL NOT BE REMOVED BEFORE THE CONCRE SUPERIMPOSED LOADS WHICH WOULD SUBSEC TO MAINTAIN AND INSURE THE INTEGRITY OF T
	3. SITE:	TOTAL SITE AREA = 6.9 ACRES TOTAL DISTURBED AREA: 6.9 ACRES	3.	FOUNDATION:
	4. THIS PROJECT IS NOT LC COUNTY, PANEL #132510	OCATED WITHIN A FLOOD HAZARD AREA ACCORDING TO FEMA FLOOD INSURANCE RATE MAP FOR SCREVEN 20215C DATED 07/22/2010.	3.1.	SUBSURFACE INFORMATION AND FOUND REPORT DATED JUNE 25, 2021. THE CON OF THE SUBGRADE UNDER THE SLAB-ON
ł	5. THIS PROJECT IS NOT LC	CATED IN A KNOWN WETLAND, AS VERIFIED THROUGH THE US FWS NATIONAL WETLANDS INVENTORY.	2.0	GEOTECHNICAL REPORT AND THE PROJE
(6. THIS PROJECT IS LOCAT WITHIN THE STATE WATE	ED WITHIN 200 FEET OF A KNOWN STATE WATERS, HOWEVER NO CONSTRUCTION ACTIVITY WILL TAKE PLACE ERS BUFFER.	5.2.	CONDITIONS AND BEARING CAPACITIES S REPORTS OF FINDINGS SHALL BE SUBMI
-	7. THE CONTRACTOR IS RE AT TIME OF PLAN ISSUAN OBTAINED PRIOR TO NO	SPONSIBLE FOR OBTAINING ANY AND ALL OFF-SITE EASEMENTS NOT DELINEATED ON PLANS OR KNOWN OF NCE; HOWEVER, EASEMENTS WITHIN THE PROPOSED PROJECT BOUNDARY HAVE BEEN OBTAINED, OR WILL BE FICE TO PROCEED, BY OWNER.	4.	CONCRETE:
ł	8. ANY DAMAGES THAT MA AT LEAST THE SAME COI RESTORATION SHALL BE ADDITIONAL COMPENSA REVEGETATION, REPLAC	Y OCCUR TO REAL PROPERTY OR EXISTING IMPROVEMENTS SHALL BE RESTORED BY THE CONTRACTOR TO NDITION THAT THE REAL PROPERTY OR EXISTING IMPROVEMENTS WERE IN PRIOR TO THE DAMAGES. THIS SUBJECT TO THE OWNER'S APPROVAL; MOREOVER, THIS RESTORATION SHALL NOT BE A BASIS FOR TION TO THE CONTRACTOR. RESTORATION SHALL INCLUDE, BUT NOT BE LIMITED TO, REGRASSING, SING FENCES, RESTORING STRUCTURES, ETC.		AGGREGATE CONFORMING TO ASTM C33 THE FOLLOWING COMPRESSIVE STRENG CONTAINMENT STRUCTURES: BASE SLABS AND MAT FOUN CONCRETE WALLS
(9. CONTRACTOR SHALL PR CONTRACTOR BELIEVES CONSTRUCTION. ANY MC SURVEYOR REGISTERED	OTECT EXISTING PROPERTY MONUMENTATION AND PRIMARY CONTROL. ANY SUCH POINTS WHICH THE WILL BE DESTROYED SHALL HAVE OFFSET POINTS ESTABLISHED BY THE CONTRACTOR PRIOR TO ONUMENTATION DESTROYED BY THE CONTRACTOR SHALL BE REESTABLISHED AT HIS EXPENSE BY A LAND O IN THE STATE OF GEORGIA.	4.2.	GROUP I CONCRETE SHALL BE USED FOR REDUCING ADDMIXTURE. GROUP I CONC OF A HIGH-RANGE WATER REDUCING AD CONTAIN A HIGH-RANGE WATER REDUCI
	10. THE CONTRACTOR SHAL AND SHALL AT ALL TIMES	L BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, AND PROCEDURES S TAKE ALL REASONABLE SAFETY PRECAUTIONS FOR THE SAFETY OF ITS EMPLOYEES ON THE PROJECT AND	4.3.	DETAILING OF CONCRETE REINFORCEME A.C.I. DETAILING MANUAL (A.C.I. SP-66).
	CONSTRUCTION CODES.	AFFLICADLE FROVISIONS OF FEDERAL, STATE, AND MUNICIFAL SAFETT LAWS AND BUILDING	4.4.	MIXING, TRANSPORTING AND PLACING O
	11. CONTRACTOR SHALL MA COURTS, TRENCHES, ET	INTAIN DRAINAGE AT ALL TIMES DURING CONSTRUCTION. PONDING OF WATER IN STREETS, DRIVES, TRUCK C. WILL NOT BE ALLOWED.	4.5.	CONCRETE REINFORCING BARS SHALL C INDICATED; IF THE LAP LENGTH IS NOT IN CORNER BARS SHALL BE PROVIDED AT A
	12. CONTRACTOR IS RESPO PREVENTION LAWS AND EXCEED ANY LOCAL, STA REQUIREMENTS ARE THI	NSIBLE FOR COMPLYING WITH ALL APPLICABLE LOCAL, STATE AND FEDERAL STORM WATER POLLUTION ORDINANCES. THE CONTRACTOR IS FULLY RESPONSIBLE FOR MAINTAINING OPERATIONS THAT MEET OR ATE OR FEDERAL PERMIT REQUIREMENTS. ANY PERMIT VIOLATION OR VIOLATIONS OF STATE LAWS AND E SOLE RESPONSIBILITY OF THE CONTRACTOR	4.6.	REINFORCING BARS AND WELDED WIRE I REQUIRED TO MAINTAIN THE CONCRETE
	13. CONTRACTOR SHALL CO AGENCY HAVING JURISD SYSTEMS, SLOPING, BEN	MPLY TO THE FULLEST EXTENT WITH THE LATEST STANDARDS OR OSHA DIRECTIVES OR ANY OTHER ICTION FOR EXCAVATION AND TRENCHING PROCEDURES. THE CONTRACTOR SHALL PROVIDE SUPPORT ICHING AND OTHER MEANS OF PROTECTION. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO, ACCESS AND	4.7.	AND LOCATED ON THE DRAWINGS. ADDIT APPROVED BY THE ENGINEER.
	EGRESS FROM ALL EXCA OSHA. 14 THE LITILITY PROTECTIO	VATION AND TRENCHING. CONTRACTOR IS RESPONSIBLE TO COMPLY WITH PERFORMANCE CRITERIA FOR	4.0.	PERCENT OF HORIZONTAL WALL REINFO IN FOOTINGS SHALL HAVE HORIZONTAL & CONSTRUCTION JOINTS IN WALL SHALL F
	15. CONTRACTOR IS TO COM	IPLY WITH ALL LOCAL BUILDING CODES AND REGULATIONS WHICH ARE PRESENTLY IN EFFECT.	4.0	KEYWAYS SHALL HAVE A DEPTH OF 1 1/2
<u> </u>	DEMOLITION NOTES		4.9.	CONCRETE SLABS-ON-GRADE OR BASE S EMT-TYPE CONDUIT AND SHALL BE PLAC SHALL BE PROHIBITED FROM EMBEDDING
	 CONTRACTOR SHALL BE WITH THE CONSTRUCTIO WATER, AND SANITARY S UTILITY RELOCATIONS. 	RESPONSIBLE FOR COORDINATION AND COST OF THE RELOCATION OF ALL UTILITIES ON SITE ASSOCIATED ON OF THIS PROJECT, SUCH AS, BUT NOT LIMITED TO DRAINAGE STRUCTURES, UTILITY POLES, GUY WIRES, SEWER, ELECTRIC CABLES, ETC. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL REQUIRED	5.	OF THE THICKNESS OF THE SLAB OR MAT CONDUIT CROSSING SHALL NOT EXCEED ANCHORS:
	2. CONTRACTOR SHALL BE FEDERAL, STATE AND LC	RESPONSIBLE FOR REMOVAL OF ALL DEBRIS AS ACCEPTABLE TO THE OWNER IN COMPLIANCE WITH ALL CAL LAWS.	5.1.	EXPANSION ANCHORS FOR FASTENING T MANUFACTURERS OR EQUAL:
Š	3. CONTRACTOR IS RESPON NOT LIMITED TO, DRAINA	NSIBLE FOR REPAIRS OF DAMAGE TO ANY EXISTING IMPROVEMENTS DURING CONSTRUCTION, SUCH AS, BUT GE, UTILITIES, PAVEMENT, STRIPING, CURBS, ETC. REPAIRS SHALL BE EQUAL TO OR BETTER THAN EXISTING		TRUBOLT WEDGE; ITW RAMSET/RED RAWL-BOLT; THE RAWLPLUG CO., INC
	 ALL AREAS NOTED ON SI EROSION CONTROL MEA SHEETS IN THIS PACKAG ALSO BE REMOVED BY C 	HEET C110-C112 SHALL BE DEMOLISHED AND REMOVED FROM THE SITE AFTER THE INSTALLATION OF SURES AND PRIOR TO BEGINNING SITE WORK. CONTRACTOR SHALL COORDINATE DEMOLITION WITH OTHER E. ITEMS REQUIRING DEMOLITION BASED ON NEW CONSTRUCTION AND NOT DETAILED ON THIS SHEET SHALL ONTRACTOR IN ACCORDANCE WITH DEMOLITION REQUIREMENTS.	5.2.	ADHESIVE/EPOXY ANCHORS FOR SETTIN THE FOLLOWING: HIT RE 500 INJECTION ADHESIVE; HIL EPCON CERAMIC 6 SYSTEM; ITW RAM SET HIGH STRENGTH EPOXY; SIMPSON ** THE USE OF THE SIMPSON SET-PA
Į	5. SAW CUT EDGES OF ASP	HALT DEMOLITION, PATCH AND REPAIR AS NECESSARY.	5.3.	ADHESIVE/EPOXY SCREEN TUBE ANCHO
(GRADING/DRAINAGE	NOTES		FOLLOWING: HIT HY 20 SYSTEM; HILTI. EPCON SYSTEM SCREEN TUBE; ITW
1	1. SITE PREPARATION: ALL STRIPPED.	TREES AND UNWANTED VEGETATION SHOULD BE REMOVED, STUMPS GRUBBED AND ORGANIC TOPSOIL	5.4.	DRILLED HOLES FOR ANCHORS SHALL BE
	2. ALL STRUCTURAL FILL SI	HOULD BE COMPACTED TO AT LEAST 95 PERCENT OF THE SOIL'S STANDARD PROCTOR MAXIMUM DRY		NECOMMENDATIONS OF THE ANCHOR M

DENSITY, AS DETERMINED BY ASTM STANDARD D-698. THE UPPER FOOT OF FILL WHICH WILL SUPPORT PAVEMENTS OR SLABS SHOULD BE COMPACTED TO AT LEAST 98 PERCENT OF THE SOIL'S STANDARD PROCTOR MAXIMUM DRY DENSITY FOR IMPROVED SUPPORT. IN AREAS WHICH ARE AT OR ABOVE THE FINISHED GRADE, AND WHICH WILL SUPPORT PAVEMENTS OR SLABS, THE UPPER 8 INCHES IMMEDIATELY BELOW THESE SYSTEMS SHOULD BE SCARIFIED AND RE-COMPACTED TO THE 98 PERCENT CRITERIA. STRUCTURAL FILL SHOULD BE FREE OF ORGANIC MATERIAL, HAVE A PLASTICITY INDEX (PI) LESS THAN 20 AND CONTAIN ROCK SIZES NO LARGER THAN 4 INCHES.

- DENSITY TESTING SHOULD BE PERFORMED BY A SOILS TECHNICIAN TO DETERMINE THE DEGREE OF COMPACTION AND VERIFY COMPLIANCE WITH THE PROJECT SPECIFICATIONS. AREAS WHICH DO NOT MEET THE COMPACTION SPECIFICATIONS SHOULD BE RE-COMPACTED TO ACHIEVE COMPLIANCE. IN CONFINED AREAS, SUCH AS UTILITY TRENCHES, THE USE OF PORTABLE COMPACTION EQUIPMENT AND THIN LIFTS OF 3 TO 4 INCHES MAY BE REQUIRED TO ACHIEVE COMPACTION.
- PERMANENT AND TEMPORARY SLOPES SHALL BE CONSTRUCTED NO STEEPER THAN 1.5H: 1V FOR SLOPES LESS THAN 15 FEET HIGH. PERMANENT SLOPES SHOULD BE CONSTRUCTED NO STEEPER THAN 2H: 1V. ALL FINISHED SLOPES SHOULD BE SUITABLY PROTECTED FROM EROSION.
- ALL CONTOURS ON PAVEMENT, OR ELSEWHERE, ARE TOP OF FINISHED PAVEMENT OR SURFACE.
- 6. SLOPES AND DISTURBED AREAS NOT COVERED BY PAVEMENT SHALL BE GRADED SMOOTH AND RECEIVE 4 INCHES OF TOPSOIL. CONTRACTOR TO PROVIDE TOPSOIL IF NOT AVAILABLE ON SITE. THE AREAS SHALL BE COVERED AS DESIGNATED ON EROSION CONTROL PLANS, FERTILIZED AND WATERED TO PROVIDE A HEARTY, MOWABLE STAND OF GRASS. SMALL ROCKS AND DEBRIS MUST BE REMOVED.

TO NOTIFY THE PROPER OFFICIALS FOR ANY REQUIRED INSPECTIONS.

UTILITY NOTES

- PROTECT INTEGRITY OF MATERIAL AND INSTALLATION.

- WITH THE APPROPRIATE UTILITY COMPANIES SPECIFICATIONS.

CTURAL WORK WITH ALL OTHER DISCIPLINES INVOLVED IN THIS PROJECT. COORDINATION INS, SLOPES, ANCHOR BOLT SETTINGS, EMBEDDED STEEL PLATES, SLEEVES FOR PIPING, BEGINS.

THE IN-SERVICE LOADS ONLY. THE METHODS, PROCEDURES AND SEQUENCES OF TY OF THE CONTRACTOR. SUPPORTING FORMWORK FOR CONCRETE CONSTRUCTION ETE HAS GAINED SUFFICIENT STRENGTH TO SAFELY SUPPORT DEAD LOADS AND EQUENTLY BE APPLIED. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS THE STRUCTURE AT ALL STAGES OF CONSTRUCTION.

DATION DESIGN ARE BASED ON A REPORT PREPARED BY WHITAKER LAB & ENGINEERING, VTRACTOR SHALL PERFORM EXCAVATIONS, FOOTING CONSTRUCTION AND PREPARATION N-GRADE IN ACCORDANCE WITH THE RECOMMENDATIONS CONTAINED IN THE IECT SPECIFICATIONS.

BEARING CAPACITIES LISTED IN THE GEOTECHNICAL REPORT. ACTUAL SUBGRADE SHALL BE VERIFIED IN THE FIELD BY A REGISTERED GEOTECHNICAL ENGINEER. WRITTEN ITTED TO INTEGRATED SCIENCE AND ENGINEERING.

SHALL HAVE NATURAL SAND FINE AGGREGATE AND NORMAL WEIGHT COARSE , TYPE I OR TYPE III PORTLAND CEMENT CONFORMING TO ASTM C 150, AND SHALL HAVE GTH (F'C) AT 28 DAYS:

JNDATIONS 4,000 PSI GROUP II CONCRETE 4,000 PSI GROUP I CONCRETE

DR LIQUID CONTAINMENT STRUCTURES AND SHALL CONTAIN A HIGH-RANGE WATER CRETE SHALL HAVE A SLUMP OF NOT GREATER THAN 2-INCHES PRIOR TO THE ADDITION DD MIXTURE. GROUP II CONCRETE SHALL BE USED FOR ALL OTHER CONCRETE AND MAY ING ADD MIXTURE, BUT IS NOT REQUIRED TO CONTAIN ONE.

IENT BARS AND ACCESSORIES SHALL CONFORM TO THE RECOMMENDATIONS OF THE

OF CONCRETE SHALL CONFORM TO A.C.I. 304R.

CONFORM TO ASTM A 615, GRADE 60. BARS NOTED AS CONTINUOUS SHALL LAP AS NDICATED THE BARS SHALL LAP THE LENGTH INDICATED IN THE LAP LENGTH SCHEDULE. ALL TURNS AND INTERSECTIONS.

FABRIC SHALL BE SUPPORTED WITH STANDARD BAR CHAIRS, BOLSTERS OR SPACERS AS E COVER INDICATED.

FOR SLABS-ON-GRADE AND BASE SLABS OR MATS AND CONCRETE WALLS ARE SHOWN ITIONAL CONTROL OR CONSTRUCTION JOINTS DESIRED BY THE CONTRACTOR MUST BE

NOLITHIC WITH ADJOINING COLUMNS, COLUMN PIERS OR PILASTERS. NO MORE THAN 50 ORCING SHALL LAP IN A SINGLE VERTICAL PLANE. BULKHEADS AT CONSTRUCTION JOINTS . KEYWAYS WITH A WIDTH EQUAL TO ONE THIRD OF THE FOOTING THICKNESS; VERTICAL . HAVE VERTICAL KEYWAYS WITH A WIDTH EQUAL TO ONE THIRD OF THE WALL THICKNESS. 2-INCHES.

ABS: TO THE GREATEST EXTENT POSSIBLE, CONDUIT SHALL NOT BE EMBEDDED IN SLABS AND MATS. IF CONDUIT MUST BE EMBEDDED WITHIN A SLAB IT SHALL BE ED WITHIN THE MIDDLE THIRD OF THE SLAB THICKNESS; PLASTIC OR PVC-TYPE CONDUIT IG IN CONCRETE. THE OVERALL SIZE OF THE CONDUIT SHALL NOT EXCEED ONE FOURTH . AVOID CROSSING OR STACKING OF EMBEDDED CONDUITS; THE OVERALL HEIGHT OF A ONE FOURTH OF THE SLAB OR MAT THICKNESS.

TO CONCRETE SHALL BE MADE OF STAINLESS STEEL AND BY ONE OF THE FOLLOWING

DHEAD.

ING DOWELS AND STAINLESS STEEL THREADED RODS IN CONCRETE SHALL BE ONE OF

MSET/REDHEAD.

SON STRONG-TIE AC SINGLE CARTRIDGE IS PROHIBITED.

ORS FOR FASTENING STAINLESS STEEL ANCHORS INTO MASONRY SHALL BE ONE OF THE

RAMSET/REDHEAD.

INSTALLED IN ACCORDANCE WITH THE WRITTEN INSTRUCTIONS AND IANUFACTURER.

1. ALL WORK SHALL CONFORM TO THE CITY OF SYLVANIA STANDARDS AND SPECIFICATIONS. IT IS THE CONTRACTOR'S RESPONSIBILITY

2. EXISTING UTILITY LOCATIONS SHOWN ARE GENERALLY SCHEMATIC IN NATURE AND MAY NOT ACCURATELY REFLECT THE SIZE AND LOCATION OF EACH PARTICULAR UTILITY. CONTRACTOR SHALL FIELD VERIFY LOCATION OF ALL EXISTING UTILITIES PRIOR TO BEGINNING CONSTRUCTION. ALL EXISTING UTILITIES MAY NOT BE SHOWN ON THESE DRAWINGS. IT IS THE CONTRACTORS RESPONSIBILITY TO COORDINATE HIS OPERATIONS WITH ALL UTILITIES WHICH MAY BE IN CONFLICT WITH HIS WORK. THE CONTRACTOR MUST MAINTAIN AND PROTECT ALL SUCH UTILITIES, OR RELOCATE UTILITIES AS NEEDED.

3. ALL WATER AND SEWER LINES OR PROCESS PIPING INSTALLED AS A PART OF THE PROJECT ARE TO BE LOCATABLE.

ALL PIPELINE CONTRACTORS MUST POSSESS AN UNDERGROUND CONTRACTORS LICENSE (UCL).

5. CITY INSPECTIONS: AUTHORIZED REPRESENTATIVES FROM THE CITY OF SYLAVANIA WILL MAKE INSPECTIONS DURING CONSTRUCTION. THIS WILL NOT RELIEVE THE OWNER OF THE RESPONSIBILITY TO SCHEDULE AN INSPECTION BEFORE WORK IS HIDDEN FROM VIEW. FAILURE TO DO SO CAN STOP WORK AND HIDDEN WORK SHALL BE EXPOSED FOR INSPECTION.

CONTRACTOR SHALL MAINTAIN A MINIMUM OF 4' COVER OVER ALL SEWER AND WATER LINES DURING CONSTRUCTION ACTIVITIES TO

7. THE MINIMUM HORIZONTAL SEPARATION BETWEEN THE CLOSEST TWO POINTS OF WATER AND SEWER LINE IS TEN FEET (10'). THE MINIMUM VERTICAL SEPARATION BETWEEN THE CLOSEST TWO POINTS OF THE WATER AND SEWER LINES IS EIGHTEEN INCHES (18").

8. CONTRACTOR SHALL COORDINATE ANY DISRUPTIONS TO EXISTING UTILITY SERVICES WITH ADJACENT PROPERTY OWNERS AND IS RESPONSIBLE FOR REPAIRS OF DAMAGE TO ANY EXISTING UTILITIES DURING CONSTRUCTION.

9. ALL ELECTRIC, TELEPHONE AND GAS LINES, INCLUDING SERVICE LINES, SHALL BE CONNECTED AND INSTALLED BY THE CONTRACTOR. THIS INCLUDES ANY PERMITTING OR CONNECTION FEES THAT MAY BE REQUIRED, ALL UTILITIES TO BE CONSTRUCTED IN ACCORDANCE

10. CONTRACTOR IS RESPONSIBLE FOR LOCATION AND PROTECTION OF ALL EXISTING UTILITIES. ANY ACCIDENTAL BREAKS OR INTERRUPTIONS IN SERVICE TO EXISTING UTILITIES, WHETHER DETAILED ON THESE DRAWINGS OR NOT, SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR, THE CONTRACTOR IS RESPONSIBLE FOR WORKING AROUND ALL UTILITIES, INCLUDING NOTIFYING ENGINEER OF ANY CONFLICTS BETWEEN NEW AND EXISTING UTILITIES PRIOR TO INSTALLATION.

LINE SYMBOLS AND ABBREVIATIONS

			FM —		— FM —	
	— FM		— FM		— FM	
		— RA	4s —		— RAS	
	— RAS	s ——	— RAS	;	— RAS	
		· \	WAS —		— WAS ·	
	- WAS	;	— WAS		— WAS ·	
	OE -		0E —	—— o	E — — -	— OE
			ss —		— ss —	
	– SS		— SS		— SS -	
			- w	·	— w —	
	— W		— w		— w —	
		· · ·				
	-x	—x—	x	x	x	—x-
						—xx-
	xx—	—xx—	—xx—	—xx—	——xx——	
	xx	—xx—	—xx—	—xx—	XX	
	xx ——	xx	xx	xx _	xx	
	xx — 	— xx — — — — — т —	— XX — — —	— XX — — — — — T —— -	— xx — — — T — — T —	
т т	XX	— XX — — — — — т — е —	— ХХ — — т — – — т — –	— XX — — — — T ———— 1 — E ——— 1	— — — — T — — T — E — — E —	т
— — — — — — — T — — — — E — —	ХХ	— XX — T — — T — E — G —	т — — — — — — — — — — — — — — —	— XX — T — — — — E — — — — — —	— — — — T — — T — E — — E — G — — G —	T - E - G -
— т — — т — — е — с —	ХХ т Е G	— XX — — — — — — — — — — — — — — — — — —	т — — — — — — — — — — — — — — —	— XX — T — — — — E — — — — — —	— — — — T — — T — E — — E — G — — G —	T EG -







ASPHALT PAVEMENT

EXISTING FORCE MAIN

SLUDGE FORCE MAIN

SLUDGE FORCE MAIN

SLUDGE FORCE MAIN

SLUDGE FORCE MAIN

EXISTING WATER MAIN

PROPOSED WATER MAIN

PROPOSED PROCESS PIPE

EXISTING STORM SEWER

PROPOSED STORM SEWER

STREAM

FENCE

SILT FENCE

HIDDEN WALL/PIPE

EXISTING ELECTRICAL

EXISTING COMMUNICATION

EXISTING NATURAL GAS MAIN

PROPOSED MAJOR CONTOUR

EXISTING MAJOR CONTOUR

EXISTING MINOR CONTOUR

CENTER LINE

PROPERTY LINE

PROPOSED MINOR CONTOUR

PROPOSED FORCE MAIN

EXISTING RETURN ACTIVATED

EXISTING WASTE ACTIVATED

PROPOSED WASTE ACTIVATED

EXISTING OVERHEAD ELECTRIC

EXISTING SANITARY SEWER

PROPOSED SANITARY SEWER

PROPOSED RETURN ACTIVATED

SUGGESTED CONSTRUCTION SEQUENCE

THE TABLE BELOW OUTLINES A SUGGESTED CONSTRUCTION SEQUENCE, WHICH IS GENERAL IN NATURE AND IS NOT CONSIDERATE OF MATERIAL AND EQUIPMENT LEAD TIMES. THE FINAL CONSTRUCTION SEQUENCE AND STARTUP SCHEDULE SHALL BE THE **CONTRACTOR'S RESPONSIBILITY**.

PHASE / ITEM	DESCRIPTION	SH
1	SECONDARY TREATMENT UPGRADES	
1.a	CONSTRUCT STAGED REACTOR AND MAKE AERATION BASIN UPGRADES	C303
1.b	INSTALL Mg(OH) CHEMICAL FEED SYSTEM	M11
1.c	STARTUP PHASED ACTIVATED SLUDGE SYSTEM WITH EX. RAS PUMPS AND PROPOSED WAS PUMPING SYSTEM TO EX. DIGESTOR	
1.d	MAKE ALL SLUDGE DEWATERING SYSTEM UPGRADES	M11
2	TERTIARY TREATMENT UPGRADES	
2.a	CONSTRUCT FILTER, PARSHALL FLUME, CHLORINE CONTACT CHAMBER, & CASCADE AERATION STRUCTURES	M10
2.b	CONSTRUCT RAS PUMP STATION WITH RAS FM TO EX. RAS FM	C30
2.c	INSTALL GRAVITY SEWER FROM MH B.1 TO RAS PS AND TEMPORARY PIPING FROM CLARIFIER #3 TO MH B.1	
2.d	REHAB CLARIFIER #3 AND BRING ONLINE WITH TEMPORARY PIPING AND STARTUP OF NEW RAS PS	
2.e	INSTALL MECHANICAL EQUIPMENT STARTUP FILTER, PARSHALL FLUME, CHLORINE CONTACT CHAMBER, AND CASCADE AERATION	M10
2.f	TAKE CLARIFIERS #1 AND #2 OFFLINE AND DEMOLISH EX. RAS PUMP ROOM	N
2.g	MAKE CLARIFIER PIPING MODIFICATIONS AND INSTALL SLUDGE COLLECTION BOX	M10
2.h	BRING ALL THREE CLARIFIERS BACK ONLINE WITH USE OF SLUDGE COLLECTION BOX AND NEW RAS PUMP STATION	
3	RESIDUALS TREATMENT UPGRADES	
3.a	CONSTRUCT NEW AEROBIC DIGESTOR, COMPLETE WITH MECHANICAL EQUIPMENT AND BRING ONLINE	M11
3.b	MAKE NECESSARY REPAIRS TO EX. AEROBIC DIGESTOR AND INSTALL NEW MECHANICAL EQUIPMENT	N

SITE FEATURE SYMBOLS

	FIRE HYDRANT
W	WATER MANHOLE
W	WATER VAULT
$\langle W \rangle$	WATER METER
\bigcirc	JUNCTION BOX
C	COMMUNICATION VAULT
Ф	UTILITY POLE
Ε	ELECTRICAL JUNCTION BOX
•	LIGHT POLE
\square	ELECTRICAL TRANSFORMER
~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	TREE
$\bigcirc$	TELECOMMUNICATION PEDESTAL
S	SANITARY SEWER MANHOLE
G	GAS METER
	THRUST BLOCK
	DROP INLET
$\bowtie$	VALVE
$\propto$	YARD HYDRANT
<u>\</u>	HYDRAULIC GRADE
$\rightarrow$	GUY WIRE

#### PIPE/MATERIAL ABBREVIATIONS

CMP	CORRUGATED METAL PIPE
HDPE	HIGH DENSITY POLYETHYLENE
RCP	REINFORCED CONCRETE PIPE
PVC	POLYVINYL CHLORIDE
DIP	DUCTILE IRON PIPE
VCP	VITRIFIED CLAY PIPE

EETS	
M100 - 102	
- M116	
- M114	
- M108	
, M109	
303	
- M108	
103	
- M105	
- M111	
111	

ENERAL	ABBREVIATIONS
BND	ABANDON
C	ACRES
LUM	
PPROX	APPROXIMATE
RV	AIR RELEASE VALVE
OB	BOTTOM OF BOX
LDG	BUILDING
	BACK FLOW PREVENTER
V AV	BALL VALVE
FMO	
Δ	FACH
FF	
L	ELEVATION
- LB	ELBOW
 P	EDGE OF PAVEMENT
SMT	EASEMENT
X	EXISTING
FE	FINISHED FLOOR ELEVATION
Н	FIRE HYDRANT
L	FLANGED
М	FORCE MAIN
AB	GRADED AGGREGATE BASE
V	GATE VALVE
w	HEADWALL
NF	INFLUENT
1V	INVERT
В	JUNCTION BOX
F	LINEAR FOOT
OD	LIMITS OF DISTURBANCE
IAX	MAXIMUM
IFR	MANUFACTURER
IIN	MINIMUM
IJ	MECHANICAL JOINT
IH	MANHOLE
С	NORMALLY CLOSED
TS	NOT TO SCALE
C	ON CENTER
ASS	PHASED ACTIVATED SLUDGE SYSTEM
E	PLAIN END
RV	PRESSURE REDUCING VALVE
S	PUMP STATION
V	PLUG VALVE
AS	RETURN ACTIVATED SLUDGE
J	RESTRAINED JOINT
/W	RIGHT OF WAY
S	STAINLESS STEEL
G	SLIDE GATE
SMH	SANITARY SEWER MAN HOLE
TD	STANDARD
TRC	STRUCTURE
	SERVICE
B	THRUST BLOCK
0 0 5	
03	TOD OF WALL
v VD	
11 ⁻ /A9	WASTE ANTIVATED SUUDAE
16 16	WEIR GATE
/M	WATER MAIN
1/	
IJEL	WAILK SUKFAUL ELEVATION

#### STRUCTURAL ABBREVIATIONS

EE	EACH END
EF	EACH FACE
EW	EACH WAY
HORZ	HORIZONTAL
T&B	TOP AND BOTTO
VERT	VERTICAL

		Science &	Fnøineerinø	QQQQQQQQ		1039 SULLIVAN ROAD, SUITE 200, NEWNAN, GEORGIA 30265	(P) 678.552.2106   (F) 678.552.2107 COA No. PEF000625   Exp. 06/30/2024
		10 kg	R IST CEREV CII	GRE	一からせいひ	1	*)
						+	e Apr.
00 1	/ 6	5	4	3	2	1 ISSUED FOR BID 4/12/2	Rev. Description Dat
Date: Drawn by: Check by:	Project #: Design by: Review by:	1521.2201 DLO DLO					
CONSTRUCTION PLANS	FOR			DIFVANIA WFUT UTUNADED			LOCATED IN SCREVEN COUNTY, GEORGIA
			GENERAL NOTES				
	DRA (	G	1	с О	^N 2	0.	





$ \begin{array}{ c c c c c c c c c c c c c c c c c c c$
CONSTRUCTION PLANS FOR SYLVANIA WPCP UPGRADES Located in screven county, georgia
EXISTING CONDITIONS SECTION 1
drawing no.







	INTEGRATED		Science &	Engineering			1039 SULLIVAN ROAD, SUITE 200, NEWNAN, GEORGIA 30265	(P) 678.552.2106   (F) 678.552.2107 COA No. PEF000625   Exp. 06/30/2024
		No an In	10 E	RIST	GERE	くういませいひ	1) 2	*)
			-		-			Apr.
							ISSUED FOR BID 4/12/	ev. Description Da
Date: Drawn by: Check by:	4/11/24 MGW DLO	Project #: Design by: Review by:	1521.2201 DLO DLO		20' 10' 0' 20'			SCALE: 1" = 20' F
	CONSTRUCTION FLANS	FOR		CVI VI ANITA W/DCD LIDCD A DEC	DIFVALUE WILL OF UNAUED			LOCATED IN SCREVEN COUNTY, GEORGIA
				DEMOLITION PLAN				
Ĩ	D	R/		'IN 1	ն 1	м 0	0.	

- NOTES: 1. ALL DEMOLITION ACTIVITIES SHALL BE COORDINATED WITH THE INSTALLATION OF NEW EQUIPMENT SO THAT THERE IS NO INTERRUPTION IN PLANT OPERATION.
- 2. CONTRACTOR SHALL COORDINATE ANY DISTURBANCE IN NORMAL PLANT OPERATION WITH OPERATIONS STAFF. 3. CONTRACTOR MAY USE BYPASS PUMPING OR INTERFERENCE MANHOLES WHERE NEEDED TO MAINTAIN PLANT FLOWS DURING CONSTRUCTION.

# NOTES: 1. ALL DEMOLITION ACTIVITIES SHALL BE COORDINATED WITH THE INSTALLATION OF NEW EQUIPMENT SO THAT THERE IS NO INTERRUPTION IN PLANT OPERATION.

- 2. CONTRACTOR SHALL COORDINATE ANY DISTURBANCE IN
- NORMAL PLANT OPERATION WITH OPERATIONS STAFF.
- 3. CONTRACTOR MAY USE BYPASS PUMPING OR INTERFERENCE MANHOLES WHERE NEEDED TO
- MAINTAIN PLANT FLOWS DURING CONSTRUCTION.





![](_page_10_Picture_0.jpeg)

![](_page_11_Picture_0.jpeg)

	INTEGRATED		Science &	Engineering			1039 SULLIVAN ROAD, SUITE 200, NEWNAN, GEORGIA 30265	(P) 678.552.2106   (F) 678.552.2107 COA NO. PEF000625   EXP. 06/30/2024
		NO SE ON	0 00 00 00 00 00 00 00 00 00 00 00 00 0	R IST CEESIV	GREAD	しいいませいど	~)~	*
							4/12/24	Date Apr.
8	7	6	5	4	3	2	1 ISSUED FOR BID	Rev. Description
Date: Drawn by: Check by:	4/11/24 MGW DLO	Project #: Design by: Review by:	1521.2201 DLO DLO		20' 10' 0' 20'			SCALE: $1^{"} = 20^{"}$
	CONSTRUCTION FLANS	FOR		CVI V/ NII A W/DCD I IDCD A DEC	DILVANIA WICI UTUNAUED			LOCATED IN SCREVEN COUNTY, GEORGIA
			DRADAGED SITE DI AN		SECTION 1			
	D	R/		'IN 2	G 0	N 1	0.	

![](_page_12_Figure_0.jpeg)

![](_page_13_Figure_0.jpeg)

![](_page_14_Picture_0.jpeg)

![](_page_15_Figure_0.jpeg)

![](_page_15_Figure_1.jpeg)

- NOTE: 1. ALL BURIED VALVES SHALL BE EQUIPPED W/ VALVE BOX & STEM I. OPERATION NUT WITHIN 6" OF FINISHED GR EXTENSION TO BRING OPERATION NUT WITHIN 6" OF FINISHED GRADE.
- VALVE BOX SHALL BE INSTALLED FLUSH W/ FINISHED GRADE. 2. ALL BURIED PIPE JOINTS SHALL BE MJ.
- 3. PROVIDE THRUST RESTRAINT AT ALL ELB AND FITTINGS BY USE OF
- RESTRAINING GLANDS. ALSO PROVIDE A MIN OF 1 FULL JOINT OF RJ ON ALL SIDES OF FITTINGS BY USE OF RESTRAINING GASKETS. 4. ALL ABOVE GROUND PIPING AND PIPE BURIED BENEATH A STRUCTURE
- SHALL BE PC 350 DIP. BURIED PIPING MAY BE SUBSTITUTED WITH C900 DR 25 PVC OR DR 11 HDPE UNLESS SPECIFIED OTHERWISE.
- 5. 10" DIP GRAVITY SEWER MAY BE SUBSTITUTED WITH 10" SDR 26 PVC.

![](_page_16_Figure_7.jpeg)

![](_page_17_Figure_0.jpeg)

68.79 68.79 162.78 Е 166.33 SE 166.33 SE 166.33 SE 166.33 SE 166.33 SE 165.66	P. 166.09 P. 166.09 P. 166.09 P. 166.09 P. 166.09 P. 100 P. 100	BAERATOR POST (TYP)		CONSTRUCTION PLANS FOR       Deter (1/1/24)       Down by (a/1/1/24)       Check by (a/1/1/24)
F-PV-1	12" PLUG VALVE (MJ/MJ)	WORM GEAR W/ OPERATING NUT & POSITION INDICATOR, N.O.	40 05 51 2.04	
F-PV-2	12" PLUG VALVE (MJ/MJ)	POSITION INDICATOR, N.C.	40 05 51 2.04	
PV-5	8" PLUG VALVE (MJ/MJ)		40 05 51 2.04	AN AN
r'V-0	ο FLUG VALVE (IMJ/MJ) 8" ΡΙ ΠΟ Ι/ΔΙ \/Ε (Μ Ι/Μ Ι)		40 05 51 2.04	J PL
' v-/ .S-P\/-7	8" PLUG VALVE (MJ/MJ)		40 05 51 2 04	NNC N 3
S-P\/-8	10" PLUG VALVE (MJ/MJ)	WORM GEAR W/ OPERATING NUT &	40 05 51 2.04 40 05 51 2 04	PIP
ω-Γν-δ Δ <u>ς</u> -Ρ\/ 1		POSITION INDICATOR, N.O.	40 00 01 2.04	EC
NO-MV-1			40 05 51 2.04	POS S
			40.05.51.0.04	ROI
NS-PV-3			40.05.51.2.04	
NS-PV-4	4" PLUG VALVE (MJ/MJ)	DIRECT NUT, N.O.	40 05 51 2.04	DRAWING NO.
S-ARV-1	2" AIR RELEASE VALVE	AUTOMATIC	40 05 51 2.07	C303
S-ARV-2	2" AIR RELEASE VALVE	AUTOMATIC	40 05 51 2.07	

![](_page_18_Figure_0.jpeg)

![](_page_18_Figure_1.jpeg)

![](_page_18_Figure_2.jpeg)

![](_page_18_Figure_3.jpeg)

![](_page_18_Figure_4.jpeg)

![](_page_18_Figure_5.jpeg)

![](_page_18_Figure_6.jpeg)

![](_page_18_Figure_7.jpeg)

![](_page_18_Figure_8.jpeg)

DIGESTOR TANK DRAIN SCALE:V=10 H=50

![](_page_19_Figure_0.jpeg)

![](_page_19_Figure_1.jpeg)

![](_page_19_Figure_2.jpeg)

		· / INTEGRATED		Science &	Engineering			1039 SULLIVAN ROAD, SUITE 200, NEWNAN, GEORGIA 30265	(P) 678.552.2106   (F) 678.552.2107 COA No. PEF000625   EXP. 06/30/2024
			No se of	0 22 00 00 00	RIST	GERE	していいませいど	A ) A	*
								2/24	ate Apr.
	8	7	6	5	4	3	2	1 ISSUED FOR BID 4/1	Rev. Description
	Date: Drawn by: Check by:	4/11/24 MGW DLO	Project #: Design by: Review by:	1521.2201 DLO DLO			SCALE: AS SHOWN		
		CONSTRUCTION FLANS	FOR		CVI VINIA WDCD I IDCD A DEC	DILVANIA WICI UTUNAUED			LOCATED IN SCREVEN COUNTY, GEORGIA
				GP A VITV SEWFR	NINA III AF MEN	PROFILES			
1.	ſ	D	R/		і З	G 0	^N 5	0.	Ĵ

![](_page_19_Figure_5.jpeg)

![](_page_19_Figure_6.jpeg)

![](_page_20_Figure_0.jpeg)

![](_page_20_Figure_1.jpeg)

<u>ut</u>		(#4	OWNER
1.	OWNER:		CITY OF 104 SOL
	CITY OF SYLVANIA		SYLVAN
	104 SOUTH MAIN ST, SYLVANIA, GEORGIA 30467		Contac
	CONTACT: STACY MATHIS		PHONE:
	(912) 564-7411		<b></b>
2.	ENGINEER/SURVEYOR:		Engi
	INTEGRATED SCIENCE & ENGINEERING INC		"I certi locatio
	1039 SULLIVAN ROAD, STE. 200		"I cert
	NEWNAN, GA 30265 CONTACT: DAVIS L OZIER, P.E		provide require
	(678) 552 - 2106		Erosior Conser
			sampli
ER	OSION. SEDIMENTATION AND		contair
PC	LLUTION CONTROL NOTES:		Design start. ⁻ start d
1.	24-HOUR CONTACT: WESLEY PARKER, 912-764-7722	(#3)	D
2.	DISTURBED AREA: 6.90 AC.; TOTAL SITE AREA: 6.90 AC.	¥5	DAVI
3.	THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBING ACTIVITIES.	<b>#19</b>	Down
4.	EROSION CONTROL MEASURES MUST BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE	(#2 <b>0</b>	"I cert
	APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.		my dir persor the pe
5.	ALL EROSION CONTROL MEASURES ARE TO CONFORM TO THE STANDARDS SET FORTH IN THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" LATEST EDITION.		gathe belief, submi violati
6.	EROSION CONTROL DEVICES SHALL BE INSTALLED BEFORE GROUND DISTURBANCE OCCURS. THE		
	THE APPROVED PLANS. IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE		PERMITTI
	EROSION CONTROL FOR ALL DRAINAGE PATTERINS, IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING CONSTRUCTION. ANY DIFFICULTY IN CONTROLLING FROSION DURING ANY PHASE OF CONSTRUCTION		
	SHALL BE REPORTED TO THE OWNER IMMEDIATELY!		(#29)
7.	ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.	(#21)	PHASE 1 E&S
8.	SEDIMENT CONTROL MEASURES MUST BE INSTALLED BEFORE CLEARING AND GRADING BEGINS.		DEMO
9.	INSPECTIONS BY QUALIFIED PERSONNEL PROVIDED BY PRIMARY PERMITEE AND THE ASSOCIATED RECORDS SHALL BE KEPT ON SITE IN COMPLIANCE WITH NPDES PERMIT NUMBER GAR 100002.		SITE WORK
10.	THE DESIGN PROFESSIONAL WHO PREPARED THE ES&PC PLAN IS TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS, PERIMETER CONTROL BMP'S, AND SEDIMENT BASINS WITHIN 7 DAYS AFTER INSTALLATION.	<b>#14</b>	CLEAN UP
11.	NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25-FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE	<b>#</b> 15	
12.	AMENDMENTS / REVISIONS TO THE ES&PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMP'S WITH A	<b>#</b> 17)	
13	THE PRIMARY PERMITTEE IS REQUIRED KEEP THE ES&PC PLAN UP-TO-DATE		
14.	STATE WATERS ARE IDENTIFIED WITHIN 200 FEET OF THE PROJECT BOUNDARIES, AS IDENTIFIED	(#4 <u>0</u>	
	HEREIN, HOWEVER, NO STATE WATERS ARE LOCATED WITHIN THE DISTURBED AREA OF THE PROJECT.	w''y	C500
15.	WASTE MATERIALS SHALL NOT BE DISCHARGED TO STATE WATERS EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.	<b>#18</b>	C501
16.	THE ES&PC PLAN IS IN COMPLIANCE WITH ALL CURRENT WASTE DISPOSAL, SANITARY SEWER, AND/OR SEPTIC TANK REGULATIONS.		C502
17.	EROSION CONTROL MATTING, Mb, IS REQUIRED ON ALL SLOPES 3:1 OR STEEPER.		C510
18.	NO ALTERNATIVE BMP'S WERE USED IN THE DESIGN OF THE ES&PC PLAN.		C600
19.	NO CONSTRUCTION ACTIVITY WILL DISCHARGE STORM WATER INTO A BIOTA IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS, ANY PORTION OF A BIOTA IMPAIRED STREAM SEGMENT. RECEIVING ARE LISTED AS IMPAIRED FOR D.O.	#22	C601
20.	ACCORDING TO 2022 303(d) LIST. CONSTRUCTION BEGINS: LONG: -81.615153 LAT: 32.764444 ENDS: LONG: -81.663822 LAT: 32.765661	(#6)	
21.	NO KNOWN WETLANDS EXIST WITHIN THE PROJECT BOUNDARIES, AS VERIFIED THROUGH THE US FWS	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
22	NATIONAL WEILANDS INVENTORY ON 6/20/2022. NO PORTION OF THIS PROPERTY'S PROJECT BOUNDARIES ARE LOCATED WITHIN A FLOOD HAZARD		
<u>-</u> <u>-</u> .	AREA ACCORDING TO F.E.M.A. FLOOD INSURANCE RATE MAP FOR SCREVEN COUNTY PANEL #13251C0215C DATED 07/22/2010.		
21. 22.	NO KNOWN WETLANDS EXIST WITHIN THE PROJECT BOUNDARIES, AS VERIFIED THROUGH THE US FWS NATIONAL WETLANDS INVENTORY ON 6/20/2022. NO PORTION OF THIS PROPERTY'S PROJECT BOUNDARIES ARE LOCATED WITHIN A FLOOD HAZARD AREA ACCORDING TO F.E.M.A. FLOOD INSURANCE RATE MAP FOR SCREVEN COUNTY PANEL #13251C0215C DATED 07/22/2010.		1039 Sullivar (p)770.46

#### nittee

**Qualified Personnel** CIVIL ENGINEER: INTEGRATED SCIENCE & ENGINEERING 1039 SULLIVAN ROAD, SUITE 200

Contact: DAVIS L OZIER, P.E. PHONE: (678) 552-2106 EXT 6001

NEWNAN, GA 30265

#### tification (#11)(#12)(#13)

y of law that this plan was prepared after a site visit to the rein by myself or my authorized agent, under my supervision.

nittee's Erosion, Sedimentation and Pollution Control Plan priate and comprehensive system of best management practices ia Water Quality Control Act and the document "Manual for Control in Georgia," (published by the State Soil and Water sion as of January 1 of the year in which the land-disturbing I, provides for the sampling of the receiving water(s) or the water outfalls and that the designed system of best s and sampling methods is expected to meet the requirements eral NPDES Permit No. GAR 100002."

f record shall inspect the site within 7 days of the construction mittee shall notify the design professional of the construction t start date.

> 11-14-22 P.E. #: 048259 GSWCC#: 0000077764

#### rtification

y of law that this document and all attachments were prepared under vision in accordance with a system designed to assure that qualified ather and evaluate the information submitted. Based upon my inquiry of who manage the system, or those persons directly responsible for ation, the information submitted is, to the best of my knowledge and and complete. I am aware that there are significant penalties for mation, including the possibility of fine and imprisonment for knowing

									-						
			ANTIC	SITE CIPATE	WORK D STAI	ACTIV	ITY SC TE - MA	HEDUL RCH 2	.E 023						
						MON	ITH								
3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18

EX
TITLE
COVER
REHENSIVE MONITORING PLAN
S CHECKLIST
AGE BASIN MAPS
PLAN - ALL PHASES
ON CONTROL DETAILS
ON CONTROL DETAILS

## EROSION, SEDIMENTATION AND POLLUTION CONTROL PLANS FOR SYLVANIA WPCP UPGRADES

![](_page_21_Picture_15.jpeg)

SCALE: 1"=1000'

ITEGRATED cience &

, Georgia 30265 301

![](_page_21_Picture_19.jpeg)

	INTEGRATED Science & Brgineering 1039 Sullivan Road, Suite 200, Newnan, Georgia 30265 (P) 678.552.2106 1 (P) 678.552.2107 COA NO, PEFOO0625 1 EXP. 06/30/2024	
	C C R C T C REGISTERED T NOT FEODOLUME MOTOFESSIONAL L-H-LA-LA-LA-LA-LA-LA-LA-LA-LA-LA-LA-LA-LA-	
	     4/12/24 Date Apr.	
	     ISSUED FOR BID	
	Drawn by: Check by: 8 MGW DLO 7 Design by: Review by: 6 DLO DLO 5 3 3 Review two 5 7 7 7 7 7 7 7 7 7 7 7 7 7 8 8 8 7 7 7 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	
#7	Date: 4/11/24 Project #: 1521.2201	]
	CONSTRUCTION PLANS FOR SYLVANIA WPCP UPGRADES Located in screven county, georgia	
	ESPC COVER	
DAVIS L. OZIER, P.E. GA PE #: 048259 GSWCC LEVEL II#: 77764	drawing no.	

![](_page_22_Picture_0.jpeg)

practices, identified on Sheet 510, include but may not be limited to silt fences, inlet sediment traps, rock filter dams, storm drain outlet protection, and other measures designed and implemented in accordance with the Manual for Erosion and Sediment Control in Georgia, latest edition. The installation of these devices may be subject to Section 404 of the CWA.

#### B. Storm Water Management

Structural measures should be placed on upland soils to the degree attainable. The installation of these devices may be subject to Section 404 of the CWA. This permit only addresses the installation of storm water management measures, and not the ultimate operation and maintenance of such structures after the construction activities have been completed and the site has undergone final stabilization. Operators are only responsible for the installation and maintenance of storm water management measures prior to final stabilization of the site, and are not responsible for maintenance after storm water discharges associated with construction activity have been eliminated from the site.

#### C. Sediment Storage

A sediment basin will not be provided on the site. The disturbed area of the site is long and slender, and there is no space for a temporary sediment basin. Without a temporary sediment basin, all sediment storage will be provided by silt fence, providing the full 67 cubic yards of sediment storage per acre drained. All storm water flow is a combination of sheet and shallow concentrated with the slopes on the site being gentle. The site will experience minimal disturbance and will be covered with debris and mulch throughout all operations.

available on-site. b. Best management practices for remediation of petroleum spills: Spill Cleanup and Control Practices procedures will be made available to site personnel. • Spill prevention practices and procedures will be reviewed after a spill and adjusted as necessary to prevent future spills. All spills will be cleaned up immediately upon discovery. Ail spills will be reported as required by local, State, and Federal regulations. 202 - 426 - 2675 E.P.D. WILL BE CONTACTED WITHIN 24 HOURS CLEANED UP AND LOCAL AGENCIES WILL BE CONTACTED AS REQUIRED. Countermeasurers Plan prepared by that licensed professional. (5) Product Specific Practices as required by local and State regulations. water discharges on the site. under a temporary roof. specifications and recommendations.

OTHER CONTROLS

authorized by a section 404 permit.

the maximum extent practical

- Concrete Truck Washing NO concrete trucks will be allowed to wash out or discharge surplus concrete or drum wash water onsite. Fertilizer/Herbicides - These products will be applied at rates that do not exceed the manufacturer's specificcitions or above the guidelines set forth in the crop establishment or in the GSWCC Manual for Erosion and Sediment Control in Georgia. Any storage of these materials will be under roof in sealed containers.
- material will be disposed of in proper waste disposal procedures.

#### 3. Inspections (#30)

#### A. Primary Permittee

- (1). Each day when any type of construction activity has taken place at a primary permittee's site, certified personnel provided by the primary permittee shall inspect: (a) all areas at the primary permittee's site where petroleum products are stored, used, or handled for spills and leaks from vehicles and equipment and (b) all locations at the primary permittee's site where vehicles enter or exit the site for evidence of off-site sediment tracking .. These inspections must be conducted until a Notice of Termination is submitted.
- (2). Measure rainfall once every 24 hours except any non-working Saturday, non-working Sunday and non-working Federal holiday until a Notice of Termination is submitted. Measurement of rainfall may be suspended if all areas of the site have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region.
- (3). Certified personnel (provided by the primary permittee) shall inspect the following at least once every seven (7) calendar days and within 24 hours of the end of a storm that is 0.5 inches rainfall or greater (unless such storm ends after 5:00 PM on any Friday or on any non-working Saturday, non-working Sunday or any non-working Federal holiday in which case the inspection shall be completed by the end of the next business day and/or working day, whichever occurs first): (a) disturbed areas of the primary permittee's construction site ; (b) areas used by the primary permittee for storage of materials that are exposed to precipitation; and (c) structural control measures. Erosion and sediment control measures identified in the Plan applicable to the primary permittee's site shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). For areas of a site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region, the permittee must comply with Part IV.D.4.a.(4). These inspections must be conducted until a Notice of Termination is submitted.
- 4). Certified personnel (provided by the primary permittee) shall inspect at least once per month during the term of this permit (i.e., until a Notice of Termination is received by EPD) the areas of the site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region. These areas shall be inspected for evidence of, or the potential for, pollutants entering the drainage system and the receiving water(s). Erosion and sediment control measures identified in the Plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s).
- (5). Based on the results of each inspection, the site description and the pollution prevention and control measures identified in the Erosion, Sedimentation and Pollution Control Plan, the Plan shall be revised as appropriate not later than seven (7) calendar days following each inspection. Implementation of such changes shall be made as soon as practical but in no case later than seven (7) calendar days following each inspection.
- (6). A report of each inspection that includes the name(s) of certified personnel making each inspection, the date(s) of each inspection, construction phase (i.e., initial, intermediate or final), major observations relating to the implementation of the Erosion, Sedimentation and Pollution Control Plan, and actions taken in accordance with Part IV.D.4.a.(5). of the permit shall be made and retained at the site or be readily available at a designated alternate location until the entire site or that portion of a construction project that has been phased has undergone final stabilization and a Notice of Termination is submitted to EPD. Such reports shall be readily available by end of the second business day and/or working day and shall identify all incidents of not been properly installed and/or maintained as described have best management practices that in the Plan. Where the report does not identify any incidents, the inspection report shall contain a certification that the best management practices are in compliance with the Erosion, Sedimentation and Pollution Control Plan. The report shall be signed in accordance with Part V.G.2. of this permit.

(1) Waste disposal. solid materials, including building materials, will not be discharged to waters of the state, except as

(2) Off-site vehicle tracking of dirt, solids, and sediments and the generation of dust will be minimized or eliminated to

(3) The permittee is in compliance with the state and local waste disposal, sanitary sewer, and septic tank regulations.

#### a. <u>Best management practices for prevention of petroleum spills</u>: All onsite vehicles will be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers that are clearly labeled. Any petroleum to be stored in tanks will have be surrounded by an earthen berm as a secondary protective measure. Any Asphalt substances used onsite will be applied according to the manufacture's recommendations. All petroleum products shall be stored and used in area that provides a secondary containment feature, and shall be located in an area with the least foreseeable impact if a catastrophic event should occur. Emergency contact numbers and procedures for spills shall be

• Local, State and manufacturer's recommended methods for spill cleanup will be clearly posted and

- Materials and equipment necessary for spill cleanup will be kept in the material storage areas. Typical materials and equipment includes, but is not limited to, brooms, dustpans, mops, rags, gloves, goggles, cat litter, sand, sawdust and properly labeled plastic and metal waste containers

#### • FOR SPILLS THAT IMPACT SURFACE WATER (LEAVE A SHEEN ON SURFACE WATER), THE NATIONAL RESPONSE CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1 _ 800 - 424 - 8802 or 1 -

#### • FOR SPILLS OF AN UNKNOWN AMOUNT, THE NATIONAL RESPONSE CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1 - 800 - 424 - 8802 or 1 - 202 - 426 - 2675. • FOR SPILLS GREATER THAN 25 GALLONS AND NO SURFACE WATER IMPACTS OCCUR, THE GEORGIA

• FOR SPILLS LESS THAN 25 GALLONS AND NO SURFACE WATER IMPACTS OCCUR, THE SPILL WILL BE

- The contractor shall notify the licensed professional who prepared this Plan if more than 1320 gallons of petroleum is stored onsite (this includes capacities of equipment) or if any one piece of equipment has a capacity greater than 660 gallons. The contractor will need a Spill Prevention Containment and
- (NOTE: CONTACT NUMBERS HAVE CHANGED. HIGHLIGHTED BOLD CONTACT NUMBERS ARE CORRECT)
- a. Petroleum Based Products Containers for products such as fuels, lubricants, and tars will be inspected daily for leaks and spills. This includes onsite vehicles and machinery daily inspections and regular preventative maintenance of such equipment. Equipment maintenance areas will be located away from State Waters, natural drains, and storm water drainage inlets. In addition, temporary fueling tanks shall have a secondary containment liner to prevent/minimize site contamination. Discharge of oils, fuels, and lubricants is prohibited. Proper disposal methods will include collection in a suitable container and disposal
- Petroleum storage shall be done in accordance with one of the two following methods to prevent storm
- a. All petroleum storage containers shall be covered in plastic sheeting or be located b. All petroleum storage containers shall be located in a secondary containment area. Paints/Finishes/Solvents - All products will be stored in tightly sealed original containers when not in use.
- Excess product will not be discharged to the storm water collection system. Excess product, materials used with these products, and product containers will be disposed of according to manufacturer's
- f. Building Materials No building or construction materials will be buried or disposed of onsite. All such
  - Cover Building materials will be stored in a staging area and covered with appropriate tarps or lean-to, to ensure no pollution of storm water can occur. All materials to be stored on stone base. All liquids, solvents, fuels, or similar to be kept in appropriate water tight containers to ensure no leakage or commingling with storm water will occur.

#### 4. Maintenance

- A. Inspections by a qualified personnel provided by the primary permittee and the associated records shall be kept on-site in compliance with GAR. 100002.
- B. Inspections of erosion control measures will be performed and corrective action taken when needed as required by the plan.
- C. The permittee shall maintain all erosion control measures until permanent vegetation has been established.
- D. The permittee shall clean out all sediment storage areas when required by the "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA".
- E. Accumulated silt shall be removed when the silt is within 12" of the top of the silt fence utilized for erosion control.

#### 5. Sampling Requirements (#31)(#33)(#34)

#### A. Sampling Requirement

Sampling will not be required on storm water flowing from the site since all runoff is sheet flow and no grading will take place as a part of this project.

#### B. Sample Type

All sampling will be collected by "grab samples" and the analysis of these samples will be conducted in accordance with methodology and test procedures established by 40 CFR Part 136 (unless other test procedures have been approved; the guidance document titled "NPDES Storm Water Sampling Guidance Document, EPA 833-B-92-001" and guidance documents that may be prepared by the EPD.

The following sampling practices will be followed in accordance with the requirements of GAR100002:

- (1) Sample containers should be labeled prior to collecting the samples.
- (2) Samples should be well mixed before transferring to a secondary container.
- (3) Large mouth, clean and rinsed glass or plastic jars should be used for collecting samples. The jars should be cleaned thoroughly to avoid contamination.
- (4) Manual, automatic or rising stage sampling may be utilized. Samples required by this permit should be analyzed immediately, but in no case later than 48 hours after collection. However, samples from automatic samplers must be collected no later than the next business day after their accumulation, unless flow through automated analysis is utilized. If automatic sampling is utilized and the automatic sampler is not activated during the qualifying event, the permittee must utilize manual sampling or rising stage sampling during the next qualifying event. Dilution of samples is not required. Samples may be analyzed directly with a properly calibrated turbidimeter. Samples are not required to be
- (5) Sampling and analysis of the receiving water(s) or outfalls beyond the minimum frequency stated in this permit must be reported to EPD as specified in Part IV.B.

#### C. <u>Sampling Points</u>

Sampling Points will be representative of the monitored activity and representative of the water quality of the receiving water(s) and/or the storm water outfalls using the following minimum guidelines:

(1) The upstream sample for each receiving water(s) will be taken immediately upstream of the confluence of the first storm water discharge from the permitted activity (i.e., the discharge farther upstream at the site) but downstream of any other storm water discharges not associated with the permitted activity. Where appropriate, several upstream samples from across the receiving water(s) may need to be taken and the arithmetic average of the turbidity of these samples used for the upstream turbidity value.

(2) The downstream sample for each receiving water(s) will be taken downstream of the confluence of

- the last storm water discharge from the permitted activity (i.e., the discharge farthest downstream at the site) but upstream of any other storm water discharge not associated with the permitted activity. Where appropriate, several downstream samples from across the receiving water(s) may need to be taken and the arithmetic average of the turbidity of these samples used for the downstream turbidity
- (3) Ideally the samples should be taken from the horizontal and vertical center of the receiving water(s) or the storm water outfall channel(s).
- (4) Care should be taken to avoid stirring the bottom sediments in the receiving water(s) or in the outfall storm water channel(s).
- (5) The sampling container should be held so that the opening faces upstream.
- (6) The samples should be kept free from floating debris.
- (7) Permittee's do not have to sample sheetflow that flows onto undisturbed natural areas or areas stabilized by the project. For purposes of this section, stabilized shall mean, for unpaved areas and areas not covered by permanent structures, 100% of the soil surface is uniformly covered in permanent vegetation with a density of 70% or greater, or equivalent permanent stabilization measures (such as the use of rip rap, gabions, permanent mulches or geotextiles) have been used. Permanent vegetation shall consist of: planted trees, shrubs, perennial vines; a crop of perennial; vegetation appropriate for the time of year and region; or a crop of annual vegetation and a seeding of target crop perennials appropriate for the region. Final stabilization applies to each phase of construction.
- (8) All sampling pursuant to this permit must be done in such a way (including generally accepted sampling methods, locations, timing, and frequency) as to accurately reflect whether storm water runoff from the facility/site is in compliance with the standard set forth in Parts III.D.4. or III.D.5., whichever is applicable.

#### D. Sampling Frequency

- (1). The primary permittee must sample in accordance with the Plan at least once for each rainfall event described below. For a qualifying event, the permittee shall sample at the beginning of any storm water discharge to a monitored receiving water and/or from a monitored outfall location within in forty-five (45) minutes or as soon as possible.
- (2). However, where manual and automatic sampling are impossible (as defined in this permit), or are beyond the permittee's control, the permittee shall take samples as soon as possible, but in no case more than twelve (12) hours after the beginning of the storm water discharge.
- (3). Sampling by the permittee shall occur for the following qualifying events:
- (a). For each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a storm water discharge that occurs during normal business hours as defined in this permit after all clearing and grubbing operations have been completed, but prior to completion of mass grading operations, in the drainage area of the location selected as the sampling location;
- (b). In addition to (a) above, for each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a storm water discharge that occurs during normal business hours as defined in this permit either 90 days after the first sampling event or after all mass grading operations have been completed, but prior to submittal of a NOT, in the drainage area of the location selected as the sampling location, whichever comes first;
- (c). At the time of sampling performed pursuant to (a) and (b) above, if BMPs in any area of the site that discharges to a receiving water or from an outfall are not properly designed, installed and maintained, corrective action shall be defined and implemented within two (2) business days, and turbidity samples shall be taken from discharges from that area of the site for each subsequent rain event that reaches or exceeds 0.5 inch during normal business hours* until the selected turbidity standard is attained, or until post-storm event inspections determine that BMPs are properly designed, installed and maintained;
- (d). Where sampling pursuant to (a), (b) or (c) above is required but not possible (or not required because there was no discharge), the permittee, in accordance with Part IV.D.4.a.(6), must include a written justification in the inspection report of why sampling was not performed. Providing this justification does not relieve the permittee of any subsequent sampling obligations under (a), (b) or (c) above; and
- (e). Existing construction activities, i.e., those that are occurring on or before the effective date of this permit, that have met the sampling required by (a) above shall sample in accordance with (b). Those existing construction activities that have met the sampling required by (b) above shall not be
- required to conduct additional sampling other than as required by (c) above. *Note that the permittee may choose to meet the requirements of (a) and (b) above by

collecting turbidity samples from any rain event that reaches or exceeds 0.5 inch and allows for sampling at any time of the day or week.

#### E. <u>Turbidity Limitations</u>

- 1. In-stream discharge is not to increase turbidity in the receiving stream by more than twenty-five (25) nephelometric units (NTU) for waters supporting warm water fisheries, as stated in GAR 100002 Part III D 4
- 2. The outfall discharge from the NPDES Sample Location Point(s) is not to exceed the maximum allowable NTU value shown below as stated in GAR 100002 Part III.D.5 and from Appendix B.

#### Turbidity Requirements for Outfall From Sediment Basin Appendix B:

SURFACE WATER DRAINAGE AREA: < 4.99 SOUARE MILES

MAXIMUM ALLOWABLE NTU = 75

SITE SIZE: 1.00 - 10 ACRES

#### 7. Reporting

- Part VI.
- b. The name(s) of the certified personnel who performed the sampling and measurements; c. The date(s) analyses were performed; d. The time(s) analyses were initiated; e. The name(s) of the certified personnel who performed the analyses;
- tapes, etc., used to determine these results; h. Results which exceed 1000 NTU shall be reported as "exceeds 1000 NTU;" and i. Certification statement that sampling was conducted as per the Plan. 3. All written correspondence required by this permit shall be submitted by return receipt certified mail (or
- similar service) to the appropriate District Office of the EPD according to the schedule in Appendix A of this permit. The permittee shall retain a copy of the proof of submittal at the construction site or the proof of submittal shall be readily available at a designated location from commencement of construction until such time as a NOT is submitted in accordance with Part VI. If an electronic submittal is provided by EPD then the written correspondence may be submitted electronically; if required, a

### **8. Retention of Records** (#32)

1. The primary permittee shall retain the following records at the construction site or the records shall be readily available at a designated alternate location from commencement of construction until such time as a NOT is submitted in accordance with Part VI: a. A copy of all Notices of Intent submitted to EPD; b. A copy of the Erosion, Sedimentation and Pollution Control Plan required by this permit; c. The design professional's report of the results of the inspection conducted in accordance with Part

- e. A copy of all inspection reports generated in accordance with Part IV.D.4.a. of this permit; f. A copy of all violation summaries and violation summary reports generated in accordance with Part III.D.2. of this permit; and
- g. Daily rainfall information collected in accordance with Part IV.D.4.a.(2). of this permit. 2. Copies of all Notices of Intent, Notices of Termination , inspection reports, sampling reports (including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation) or other reports requested by the EPD, Erosion, Sedimentation and Pollution Control Plans, records of all data used to complete the Notice of Intent to be covered by this permit and all other records required by this permit shall be retained by the permittee who either produced or used it for a period of at least three years from the date that the NOT is submitted in accordance with Part VI. of this permit. These records must be maintained at the permittee's primary place of business or at a
- designated alternative location once the construction activity has ceased at the permitted site. This

1. The applicable permittees are required to submit the sampling results to the EPD at the address shown in Part II.C. by the fifteenth day of the month following the reporting period. Reporting periods are months during which samples are taken in accordance with this permit. Sampling results shall be in a clearly legible format. Upon written notification, EPD may require the applicable permittee to submit the sampling results on a more frequent basis. Sampling and analysis of any storm water discharge(s) or the receiving water(s) beyond the minimum frequency stated in this permit must be reported in a similar manner to the EPD. The sampling reports must be signed in accordance with Part V.G.2. Sampling reports must be submitted to EPD until such time as a NOT is submitted in accordance with

2. All sampling reports shall include the following information:

- a. The rainfall amount, date, exact place and time of sampling or measurements;
- f. References and written procedures, when available, for the analytical techniques or methods used; g. The results of such analyses, including the bench sheets, instrument readouts, computer disks or
- paper copy must also be submitted by return receipt certified mail or similar service.
- IVA5. of this permit;
- d. A copy of all sampling information, results, and reports required by this permit;
- period may be extended by request of the EPD at any time upon written notification to the permittee. 9. Report Submittal
- All written correspondence required by this permit shall be submitted by *return receipt certified mail* (or similar service) to the appropriate District Office of the EPD. See address below:
  - EAST CENTRAL DISTRICT 3525 WALTON WAY EXT. **AUGUSTA, GA. 30909** PHONE (706) 667-4343

![](_page_22_Picture_113.jpeg)

(#1)

		EROSION, SEDIMENTATIO	ON & POLLUTION CONTROL PLAN CHECKLIST
			E CONSTRUCTION PROJECTS HEE RIVER - REGION 3
Project	Name: S	YLVANIA WPCP UPGRADES	Address: 624 FRIENDSHIP RD
City/Co	ounty: <u>S</u>	SYLVANIA / SCREVEN	Date on Plans: <u>11/14/2022</u>
Name 8	& email of	person filling out checklist:	DAVIS OZIER, dozier@intse.com
Plan	Included	TO BE	SHOWN ON ES&PC PLAN
Page #	Y/N	1 The applicable Eresian Sedimentati	an and Ballutian Cantral Dian Charlelint astablished by the Commission on of January 1
C502	Y	of the year in which the land-disturbi	ng activity was permitted
		(The completed Checklist must be su	Ibmitted with the ES&PC Plan or the Plan will not be reviewed)
C500	Υ	2 Level II certification number issued b	y the Commission, signature and seal of the certified design professional.
6500		(Signature, seal and level II number	must be on each sheet pertaining to ES&PC Plan or the Plan will not be reviewed)
C500	Y	3 The name and phone number of the	24-nour contact responsible for erosion, sedimentation and pollution controls.
C500		5 Note total and disturbed acreages of	the project or phase under construction
C500		6 Drouido the CDS lessitions of the her	vipping and and of the Infrastructure project. Give the Leftude and Lengitude in
		decimal degrees.	Jinning and end of the millast downe project. Give the callede and conglidde in
C500	Υ	7 Initial date of the Plan and the dates of	of any revisions made to the Plan including the entity who requested the revisions.
C501	Υ	8 Descriptions of the nature of construct	ction activity and existing site conditions.
C500	Υ	9 Provide vicinity map showing site's r	elation to surrounding areas. Include designation of specific phase, if necessary.
C501	Υ	10 Identify the project receiving waters a wetlands, marshlands, etc. which ma	and describe all sensitive adjacent areas including streams, lakes, residential areas, ay be affected.
C500	Y	11 Design professional's certification sta Plan as stated on <b>Part IV page 21</b> c	tement and signature that the site was visited prior to development of the ES&PC of the permit
C500	Υ	12 Design professional's certification sta and comprehensive system of BMPs	tement and signature that the permittee's ES&PC Plan provides for an appropriate s and sampling to meet permit requirements as stated on <b>Part IV page 20</b> of the permit *
C500	Υ	13 Design professional certification state sampling as stated on <b>Part IV.D.6.c.</b>	ement and signature that the permittee's ES&PC Plan provides for representative .(3) page 37 of the permit as applicable. *
C500	Υ	14 Clearly note the statement that "The initial sediment storage requirements in accordance with <b>Part IV.A.5 page</b>	design professional who prepared the ES&PC Plan is to inspect the installation of the , perimeter control BMPs, and sediment basins within 7 days after installation." <b>e 26</b> of the permit. *
C500	Υ	15 Clearly note the statement that "Non- buffers as measured from the point o from the Jurisdictional Determination	exempt activities shall not be conducted within the 25 or 50-foot undisturbed stream If wrested vegetation or within 25-feet of the coastal marshland buffer as measured Line without first acquiring the necessary variances and permits."
C501	Υ	16 Provide a description of any buffer e	ncroachments and indicate whether a buffer variance is required.
C500	Υ	17 Clearly note the statement that "Amer hydraulic component must be certifie	ndments/revisions to the ES&PC Plan which have a significant effect on BMPs with a d by the design professional." *
C500	Υ	18 Clearly note the statement that "Wast Section 404 permit." *	e materials shall not be discharged to waters of the State, except as authorized by a
C500	Υ	19 Clearly note statement that "The esc sediment control measures and prac	ape of sediment from the site shall be prevented by the installation of erosion and tices prior to land disturbing activities."
C500	Υ	20 Clearly note statement that "Erosion Plan does not provide for effective en to control or treat the sediment source	control measures will be maintained at all times. If full implementation of the approved rosion control, additional erosion and sediment control measures shall be implemented e."
C500	Υ	21 Clearly note the statement "Any distu or temporary seeding."	rbed area left exposed for a period greater than 14 days shall be stabilized with mulch
	N/A	22 Any construction activity which disch of and within the same watershed as permit Include the completed Apper to the Impaired Stream Segment *	arges storm water into an Impaired Stream Segment, or within 1 linear mile upstream a, any portion of a Biota Impaired Stream Segment must comply with Part III. C. of the ndix 1 listing all the BMPs that will be used for those areas of the site which discharge
	N/A	23 If a TMDL Implementation Plan for se above) at least six months prior to su requirements included in the TMDL	ediment has been finalized for the Impaired Stream Segment (identified in item 22 ubmittal of NOI, the ES&PC Plan must address any site-specific conditions or Implementation Plan. *
C501	Υ	24 BMPs for concrete washdown of too at the construction site is prohibited.	ls, concrete mixer chutes, hoppers and the rear of the vehicles. Washout of the drum $\star$
C501	Υ	25 Provide BMPs for the remediation of	all petroleum spills and leaks.
C501	Y	26 Description of the measures that will	be installed during the construction process to control pollutants in storm water that
C501	v	27 Description of practices to provide or	is nave been completed.
COUL			www.www.www.www.www.www.www.www.www.ww

C501	Y
C500	Y

C501

C501

C501 C501

C501

C503

С503 Y С503 Y С503 Y

C510 Y C510 Y

C501

0540

8	Description of the practices that will be used to reduce the pollutants in storm water discharges. *
9	Description and chart or timeline of the intended sequence of major activities which disturb soils for the major portions of the site (i.e., initial perimeter and sediment storage BMPs, clearing and grubbing activities, excavation activities, utility activities, temporary and final stabilization).
0	Provide complete requirements of Inspections and record keeping by the primary permittee. *
1	Provide complete requirements of Sampling Frequency and Reporting of sampling results. st
2	Provide complete details for Retention of Records as per Part IV.F. of the permit $$ *
3	Description of analytical methods to be used to collect and analyze the samples from each location. $*$

33 Description of analytical methods to be used to collect and analyze the samples from each	locatio
----------------------------------------------------------------------------------------------	---------

34 Appendix B rationale for NTU values at all outfall sampling points where applicable.  st 

#### 35 Delineate all sampling locations, perennial and intermittent streams and other water bodies into which storm water is discharged also provide a summary chart of the justification and analysis for the representative sampling as applicable. *

C501 Y	36 A description of appropriate controls and measures that will be implemented at the construction site including: (1) initial
	sediment storage requirements and perimeter control BMPs, (2) intermediate grading and drainage BMPs, and (3) final
	BMPs. For construction sites where there will be no mass grading and the initial perimeter control BMPs,
	intermediate grading and drainage BMPs, and final BMPs are the same, the Plan may combine all of the BMPs into a single

phase. *

C510 Y	37 Graphic scale and North a	rrow.	
C510 Y	38 Existing and proposed cor	ntour lines with contour lines drawn at an interval in acc	ordance with the following:
	Existing Contours	USGS 1": 2000' Topographical Sheets	]
	Proposed Contours	1" : 400' Centerline Profile	]
N/A	39 Use of alternative BMPs w as certified by a Design Pr Commission). Please refe	hose performance has been documented to be equiva ofessional (unless disapproved by GAEPD or the Geo r to the Alternative BMP Guidance Document found at v	lent to or superior to conventional BMPs rgia Soil and Water Conservation www.gaswcc.georgia.gov.
N/A	40 Use of alternative BMP for Erosion & Sediment Contro	application to the Equivalent BMP List. Please refer to a	Appendix A-2 of the Manual for
C510 Y	41 Delineation of the applicable	le 25-foot or 50-foot undisturbed buffers adjacent to Sta	te waters and any additional buffers

required by the Local Issuing Authority. Clearly note and delineate all areas of impact

42 Delineation of on-site wetlands and all State waters located on and within 200 feet of the project site.

43 Delineation and acreage of contributing drainage basins on the project site.

44 Delineate on-site drainage and off-site watersheds using USGS 1" :2000' topographical sheets.

45 An estimate of the runoff coefficient or peak discharge flow of the site prior to and after construction activities are completed.

N/A 46 Storm-drain pipe and weir velocities with appropriate outlet protection to accommodate discharges without erosion. Identify/Delineate all storm water discharge points.

47 Soil series for the project site and their delineation.

48 The limits of disturbance for each phase of construction.

C510 Y 49 Provide a minimum of 67 cubic yards of sediment storage per acre drained using a temporary sediment basin, retrofitted detention pond, and/or excavated inlet sediment traps for each common drainage location. Sediment storage volume must be in place prior to and during all land disturbance activities until final stabilization of the site has been achieved. A written justification explaining the decision to use equivalent controls when a sediment basin is not attainable must be included in the Plan for each common drainage location in which a sediment basin is not provided. A written justification as to why 67 cubic yards of storage is not attainable must also be given. Worksheets from the Manual must be included for structural BMPs and all calculations used by the design professional to obtain the required sediment storage when using equivalent controls. When discharging from sediment basins and impoundments, permittees are required to utilize outlet structures that withdraw water from the surface, unless infeasible. If outlet structures that withdraw water from the surface are not feasible, a written justification explaining this decision must be included in the Plan.

C510 Y 50 Location of Best Management Practices that are consistent with and no less stringent than the Manual for Erosion and Sediment Control in Georgia. Use uniform coding symbols from the Manual, Chapter 6, with legend.

C601 Y 51 Provide detailed drawings for all structural practices. Specifications must, at a minimum, meet the guidelines set forth in the Manual for Erosion and Sediment Control in Georgia.

C600 Y 52 Provide vegetative plan, noting all temporary and permanent vegetative practices. Include species, planting dates and seeding, fertilizer, lime and mulching rates. Vegetative plan shall be site specific for appropriate time of year that seeding will take place and for the appropriate geographic region of Georgia.

* If using this checklist for a project that is less than 1 acre and not part of a common development

but within 200 ft of a perennial stream, the  *  checklist items would be N/A.

Effective January 1, 2022

	1039 SULLIVAN ROAD, SUITE ZOO, NEWNAN, GEORGIA 30265
	C R C C R C R C R C R C R C R C R C R C R C R C R C R C R C R C R C R C R C R C R C R C R C R C R C R C
	    4/12/24 Date Apr.
	<ul> <li>8</li> <li>7</li> <li>6</li> <li>5</li> <li>4</li> <li>3</li> <li>3</li> <li>2</li> <li>1 ISSUED FOR BID</li> <li>Rev. Description</li> </ul>
	Date:Drawn by:Check by:4/11/24MGWDLOProject #:Design by:Review by:1521.2201DLODLO
	CONSTRUCTION PLANS FOR SYLVANIA WPCP UPGRADES Located in Screven county, georgia
	CHECKLIST
DAVIS L. OZIER, P.E. GA PE #: 048259 GSWCC LEVEL II#: 77764	drawing no.

#2

![](_page_24_Figure_0.jpeg)

![](_page_24_Picture_2.jpeg)

#### SEDIMENT STORAGE SUMMARY

PROJECT SITE SEDIMENT STORAGE BASIN A					
SUB-DRAINAGE	DISTURBED	REQUIRED SEDIMENT	SEDIMENT STORAGE PROVIDED (CY)		
AREA (AC)	AREA (AC)	STORAGE (CT)	SILT FENCE (.3CY/FT)		
5.0	4.42	119.34	125		

PROJECT SITE SEDIMENT STORAGE BASIN B						
SUB-DRAINAGE	DISTURBED	REQUIRED SEDIMENT	SEDIMENT STORAGE PROVIDED (CY)			
AREA (AC)	AREA (AC)	STORAGE (CY)	SILT FENCE (.3CY/FT)			
7.50	2.56	69.12	80			

#### PHASES I&II

#### STRUCTURAL PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION	#50
Sd1	SEDIMENT BARRIER		(INDICATE TYPE)	A barrier to prevent sediment from leaving the construction site. It may be sandbags, bales of straw or hay, brush, logs and poles, gravel, or a silt fence.	
Co	CONSTRUCTION EXIT		(LABEL)	A crushed stone pad located at the construction site exit to provide a place for removing mud from tires thereby protecting public streets.	
Sd2	INLET SEDIMENT TRAP	v v z v v v v v v v v v v v v v v v v v		An impounding area created by excavating around a storm drain drop inlet. The excavated area will be filled and stabilized on completion of construction activities.	

#### VEGETATIVE PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Ds1	DISTURBED AREA STABILIZATION (WITH MULCHING ONLY)	() () () () () () () () () () () () () (	Ds1	Establishing temporary protection for disturbed areas where seedlings may not have a suitable growing season to produce an erosion retarding cover.
Ds2	DISTURBED AREA STABILIZATION (WITH TEMP SEEDING)		Ds2	Establishing a temporary vegetative cover with fast growing seedings on disturbed areas.
Ds3	DISTURBED AREA STABILIZATION (WITH PERM SEEDING)	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	Ds3	Establishing a permanent vegetative cover such as trees, shrubs, vines, grasses, or legumes on disturbed areas.

#### PHASE III

#### VEGETATIVE PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Ds3	DISTURBED AREA STABILIZATION (WITH PERM SEEDING)	1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.	Ds3	Establishing a permanent vegetative cover such as trees, shrubs, vines, grasses, or legumes on disturbed areas.

	SOIL SERIES	#47
BeB	BLANTON SAND: 0%-5% SLOPES	
FuA	FUQUAY LOAMY SAND: 0%–2% SLOPES, FREQUENTLY FLOODED	
KBA	KINSTON AND BIBB SOILS, 0%-2% SLOPES, FREQUENTLY FLOODED	
NcC2	NANKIN–COWARTS COMPLEX, 5%–8% SLOPES, ERODED	

#49

![](_page_25_Figure_13.jpeg)

Ds1 MULCHING SPECIFICATIONS:

MULCH OR TEMPORARY GRASSING SHALL BE APPLIED TO ALL EXPOSED AREAS WITHIN 14 DAYS OF DISTURBANCE. MULCH CA	N
BE USED AS A SINGULAR EROSION CONTROL DEVICE FOR UP TO SIX MONTHS, BUT IT SHALL BE APPLIED AT THE	
APPROPRIATE DEPTH, DEPENDING ON THE MATERIAL USED, ANCHORED, AND HAVE CONTINUOUS 90% COVER OR GREATER (	ЭF
THE SOIL SURFACE. MAINTENANCE SHALL BE REQUIRED TO MAINTAIN APPROPRIATE DEPTH AND 90% COVER. TEMPORARY	
VEGETATION MAY BE EMPLOYED INSTEAD OF MULCH IF THE AREA WILL REMAIN UNDISTURBED FOR LESS THAN SIX MONTHS. I	IF
AN AREA WILL REMAIN UNDISTURBED FOR GREATER THAN SIX MONTHS, PERMANENT VEGETATION TECHNIQUES SHALL BE	
EMPLOYED.	

SITE PREPARATION 1. GRADE TO PERMIT THE USE OF EQUIPMENT FOR APPLYING AND ANCHORING MULCH. 2. INSTALL NEEDED EROSION CONTROL MEASURES AS REQUIRED SUCH AS DIKES, DIVERSIONS, BERMS, TERRACES, AND SEDIMENT BARRIERS.

3. LOOSEN COMPACT SOIL TO A MINIMUM DEPTH OF 3 INCHES.

4. APPLY POLYETHYLENE FILM ON EXPOSED AREAS.

APPLYING MULCH WHEN MULCH IS USED WITHOUT SEEDING, MULCH SHALL BE APPLIED TO PROVIDE FULL COVERAGE OF THE EXPOSED AREA. 1. DRY STRAW OR HAY MULCH AND WOOD CHIPS SHALL BE APPLIED UNIFORMLY BY HAND OR BY MECHANICAL EQUIPMENT. 2. IF THE AREA WILL EVENTUALLY BE COVERED WITH PERENNIAL VEGETATION, 20-30 POUNDS OF NITROGEN PER ACRE IN ADDITION TO THE NORMAL AMOUNT SHALL BE APPLIED TO OFFSET THE UPTAKE OF NITROGEN CAUSED BY THE DECOMPOSITION OF THE ORGANIC MULCHES. 3. CUTBACK ASPHALT SHALL BE APPLIED UNIFORMLY . CARE SHOULD BE TAKEN IN AREAS OF PEDESTRIAN TRAFFIC DUE TO PROBLEMS OF "TRACKING IN" OF DAMAGE TO SHOES, CLOTHING, ETC.

ANCHORING MULCH 1. STRAW OR HAY MULCH CAN BE PRESSED INTO THE SOIL WITH A DISK HARROW WITH THE DISK SET STRAIGHT OR WITH A SPECIAL "PACKER DISK". DISKS MAY BE SMOOTH OR SERRATED AND SHOULD BE 20 INCHES OR MORE IN DIAMETER AND 8 TO 12 INCHES APART. THE EDGES OF THE DISK SHOULD BE DULL ENOUGH NOT TO CUT THE MULCH BUT TO PRESS IT INTO THE SOIL LEAVING MUCH OF IT IN AN ERECT POSITION. STRAW OR HAY MULCH SHALL BE ANCHORED IMMEDIATELY AFTER APPLICATION. STRAW OR HAY MULCH SPREAD WITH SPECIAL BLOWER-TYPE EQUIPMENT MAY BE ANCHORED WITH EMULSIFIED ASPHALT (GRADE AE-5 OR SS-1). THE ASPHALT EMULSION SHALL BE SPRAYED ONTO THE MULCH AS IT IS EJECTED FROM THE MACHINE. USE 100 GALLON'S OF EMULSIFIED ASPHALT AND 100 GALLONS OR WATER PER TON OF MULCH. TACKIFIERS AND BINDERS CAN BE SUBSTITUTED FOR EMULSIFIED ASPHALT. PLEASE REFER TO SPECIFICATION Tb-TACKIFIERS AND BINDERS. PLASTIC MESH OR NETTING WITH MESH NO LARGER THAN ONE INCH BY ONE INCH SHALL BE INSTALLED ACCORDING TO

MANUFACTURER'S SPECIFICATIONS. 2. NETTING OF THE APPROPRIATE SIZE SHALL BE USED TO ANCHOR WOOD WASTE. OPENINGS OF THE NETTING SHALL NOT BE LARGER THAN THE AVERAGE SIZE OF THE WOOD WASTE CHIPS. 3. POLYETHYLENE FILM SHALL BE ANCHOR TRENCHED AT THE TOP AS WELL AS INCREMENTALLY AS NECESSARY.

Ds2 TEMPORARY SEEDING SPECIFICATIONS:

A. GRADING AND SHAPING

1. EXCESSIVE WATER RUNOFF MUST BE CONTROLLED BY PLANNED AND INSTALLED EROSION CONTROL PRACTICES SUCH AS CLOSED DRAINS, DITCHES, DIKES, DIVERSIONS, SEDIMENT BASINS, AND OTHERS.

B. SEEDBED PREPARATION

1. WHEN A HYDRAULIC SEEDER IS USED, SEEDBED PREPARATION IS NOT REQUIRED. 2. WHEN USING CONVENTIONAL OR HAND-SEEDING, SEEDBED PREPARATION IS NOT REQUIRED IF THE SOIL MATERIAL IS LOOSE AND NOT SEALED BY RAINFALL. 3. WHEN SOIL HAS BEEN SEALED BY RAINFALL OR CONSISTS OF SMOOTH UNDISTURBED CUT SLOPES, THE SOIL SHALL BE PITTED, TRENCHED, OR OTHERWISE

SCARIFIED TO PROVIDE A PLACE FOR SEED TO LODGE AND GERMINATE.

C. LIME AND FERTILIZER

1. AGRICULTURAL LIME IS NOT REQUIRED.

2. ON REASONABLY FERTILE SOILS OR SOIL MATERIAL, FERTILIZER IS NOT REQUIRED. 3. ON SOILS OF VERY LOW FERTILITY, USE 500 TO 700 POUNDS 10-10-10 FERTILIZER OR THE EQUIVALENT PER ACRE (12-16 lbs./1000 sq. ft.). IF THE SITE WILL PERMIT,

ÀPPLY BEFORE LAND PREPARATION AND DISK, RIP, OR CHISEL TO INCORPORATE.

D. SEEDING

1. SELECT A GRASS OR GRASS-LEGUME MIXTURE SUITABLE TO THE AREA AND SEASON OF THE YEAR. 2. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER-SEEDER, OR HYDRAULIC SEEDER (SLURRY INCLUDING SEED AND FERTILIZER).

DRILL OR CULTIPACKER-SEEDERS SHOULD NORMALLY PLACE SEED ONE-HALF TO ONE INCH DEEP.

E. MULCHING TEMPORARY VEGETATION CAN, IN MOST CASES, BE ESTABLISHED WITHOUT THE USE OF MULCH. MULCH WITHOUT SEEDING SHOULD BE CONSIDERED FOR SHORT TERM PROTECTION. SEE Ds1 - DISTURBED AREA STABILIZATION (WITH MULCHING ONLY).

-. IRRIGATION

IF WATER IS APPLIED, IT MUST BE AT A RATE NOT CAUSING RUNOFF AND EROSION. THOROUGHLY WET THE SOIL TO A DEPTH THAT WILL INSURE GERMINATION OF THE SEED. SUBSEQUENT APPLICATIONS SHOULD BE MADE WHEN NEEDED.

* REVISED 7/01 PER 5TH EDITION OF MANUAL FOR EROSION & SEDIMENT CONTROL IN GEORGIA.

PERMANENT SEEDING SPECIFICATIONS:

Ds3

A. GRADING AND SHAPING 1. GRADING AND SHAPING IS NOT NORMALLY REQUIRED WHERE HYDRAULIC SEEDING AND FERTILIZING EQUIPMENT IS TO BE USED. VERTICAL BANKS SHALL BE SLOPED TO ENABLE PLANT ESTABLISHMENTS.

B. SEEDBED PREPARATION I. SEEDBED PREPARATION MAY NOT BE REQUIRED WHERE HYDRAULIC SEEDING AND FERTILIZING EQUIPMENT IS TO BE USED. 2. WHEN CONVENTIONAL SEEDING IS TO BE USED, SEEDBED PREPARATION WILL BE DONE AS FOLLOWS: A. BROADCAST PLANTING

1. TILLAGE AT A MINIMUM, SHALL ADEQUATELY LOOSEN THE SOIL TO A DEPTH OF 4 TO 6 INCHES: ALLEVIATE COMPATION; INCORPORATE LIME AND FERTILIZER; SMOOTH AND FIRM THE SOIL; ALLOW FOR THE PROPER PLACEMENT OF SEED SPRIGS, OR PLANTS; AND ALLOW FOR THE ANCHORING OF STRAW OR HAY MULCH IF A DISK IS TO BE USED.

C. LIME AND FERTILIZER - RATES AND ANALYSIS 1. WHERE PERMANENT VEGETATION IS TO BE ESTABLISHED, AGRICULTURAL LIME SHALL BE APPLIED AS INDICATED BY SOIL TEST OR AT THE RATE OF 1 TO 2 TONS PER ACRE. AGRICULTURAL LIME SHALL BE WITHIN THE SPECIFICATIONS OF THE GEORGIA DEPARTMENT OF AGRICULTURE. 2. LIME SPREAD BY CONVENTIONAL EQUIPMENT WILL BE "GROUND LIMESTONE". GROUND LIMESTONE IS CALCITIC OR DOLOMITIC

LIMESTONE GROUND SO THT 90 PERCENT OF THE MATERIAL WILL PASS THROUGH A 10-MESH SIEVE AND NOT LESS THAN 25 PERCENT WILL PASS THROUGH A 100-MESH SIEVE. 3. AGRICULTURAL LIME SPREAD BY HYDRAULIC SEEDING EQUIPMENT WILL BE "FINELY GROUND LIMESTONE." FINELY GROUND LIMESTONE IS CALCITIC OR DOLOMITIC LIMESTONE GROUND SO THAT 98 PERCENT OF THE MATERIAL WILL PASS THROUGH A 20-MESH SIEVE AND NOT LESS THAN 70 PERCENT WILL PASS THROUGH A 100-MESH SIEVE.

D. LIME AND FERTILIZER - APPLICATION 1. WHEN HYDRAULIC SEEDING EQUIPMENT IS USED:

A. THE INITIAL FERTILIZER WILL BE MIXED WITH SEED, INOCULANT (IF NEEDED) AND WOOD CELLULOSE OR WOOD PULP

FIBER MULCH AND APPLIED IN A SLURRY. THE SLURRY WILL BE AGITATED DURING APPLICATION TO KEEP THE INGREDIENTS THOROUGHLY MIXED. THE MIXTURE WILL BE SPREAD UNIFORMLY OVER THE AREA WITHIN ONE HOUR AFTER BEING PLACED IN THE HYDROSEEDER.

B. FINELY GROUND LIMESTONE WILL BE MIXED WITH WATER AND APPLIED IMMEDIATELY AFTER MULCHING IS COMPLETED OR IN COMBINATION WITH THE TOP DRESSING.

2. WHEN CONVENTIONAL PLANTING IS TO BE DONE, LIME AND FERTILIZER WILL BE APPLIED UNIFORMLY IN ONE OF THE FOLLOWING WAYS:

- A. APPLY BEFORE LAND PREPARATION SO THAT IT WILL BE MIXED WITH THE SOIL DURING SEEDBED PREPARATION; OR, B. MIX WITH THE SOIL USED TO FILL THE HOLES, DISTRIBUTE IN FURROWS; OR,
- C. BROADCAST AFTER STEEP SURFACES AND SCARIFIED, PITTED OR TRENCHED. D. A FERTILZER PELLET WILL BE PLACED AT ROOT DEPTH.

* REVISED 7/01 PER 5TH EDITION OF MANUAL FOR EROSION & SEDIMENT CONTROL IN GEORGIA.

(LOLIUM ALONE 

ALONE MILLET, (PANICUI

ALONE IN MIXTU

WITH OTH

	Ds2	DISTURBE	) AREA STA	BILIZATION (WITH TEMPORAR	Y SEEDINGS)
SPECIES	BROA RATES 2/ PER	DCAST - PLS 3/ PER	RESOURCE AREA	PLANTING RATES BY RESOURCE AREA PLANTING DATES OPTIMUM PERMISSIBLE BUT MARGINAL	REMARKS
MILLET, PEARL (PENNESETUM GLAUCUM) ALONE	50 LBS	1.1 LB	M-L P C		88,000 SEED PER POUND. QUICK DENSE COVER. MAY REACH 5 FEET IN HEIGHT. NOT RECOMMENDED FOR MIXTURES.
RYEGRESS, ANNUAL (LOLIUM TEMULENTUM) ALONE	40 LBS	0.9 LB	M-L P C		227,000 SEED PER POUND. DENSE COVER. VERY COMPETITIVE VERY COMPETITIVE AND IS NOT TO BE USED IN MIXTURES
SUDANGRASS (SORGHUM SUDANESE) ALONE	60 LBS	1.4 LB	M-L P C		55,000 SEED PER POUND. GOOD ON DROUGHTY SITES. NOT RECOMMENDED FOR MIXTURES.
MILLET, BROWNTOP (PANICUM FASCICULATUM) ALONE IN MIXTURES	40 LBS 10 LBS	0.9 LB 0.2 LB	M-L P C		137,000 SEED PER POUND. QUICK DENSE COVER. WILL PROVIDE TOO MUCH COMPETITION IN MIXTURES IF SEEDED AT HIGH RATES.

	Ds3	DISTURBE	D AREA STA	BILIZATION (WITH PERMANE	NT SEEDINGS)	
SPECIES	BROADCAST RATES 2/ – PLS 3/		DECOMPOS	PLANTING RATES BY RESOURCE AREA PLANTING DATES OPTIMUM	REMARKS	
	PER ACRE	PER 1000 SQ. FT.	AREA	PERMISSIBLE         BUT         MARGINAL           J         F         M         A         J         J         A         S         O         N         D		
BERMUDA, COMMON (CYNODON DACTYLON) HULLED SEED ALONE WITH OTHER PERENNIALS	10 LBS 6 LBS	0.2 LB 0.1 LB	P C		1,787,000 SEED PER POUND. QUICK COVER. LOW GROWING AND SOD FORMING. FULL SUN. GOOD FOR ATHLETIC FIELDS.	
BERMUDA, COMMON (CYNODON DACTYLON) UNHULLED SEED			P C			
WITH TEMPORARY COVER WITH OTHER PERENNIALS	10 LBS 6 LBS	0.2 LB 0.1 LB			PLANT WITH WINTER ANNUALS. PLANT WITH TALL FESCUE.	
CENTIPEDE (EREMOCHLOA OPHIUROIDES)	BLOCK S	OD ONLY	P C		DROUGHT TOLERANT. FULL SUN OR PARTIAL SHADE. EFFECTIVE ADJACENTTO CONCRETE AND IN CONCENTRATED FLOW AREAS. IRRIGATION AS NEEDED UNTIL FULLY ESTABLISHED. DO NOT PLANT NEAR PASTURES. WINTERHARDY AS FAR NORTH AS ATHENS AND ATLANTA.	
FESCUE, TALL (FESTUCA ARUNDINACEA) ALONE WITH OTHER PERENNIALS	50 LBS 30 LBS	1.1 LB 0.7 LB	M-L P		227,000 SEED PER POUND. USE ALONE ONLY ON BETTER SITES. NOT FOR DROUGHTY SOILS. MIX WITH PERENNIAL LESPEDEZAS OR CROWNVETCH. APPLY TOPDRESSING IN SPRING FOLLOWING FALL PLANTINGS. NOT FOR HEAVY USE AREAS OR ATHLETIC FIELDS.	
LESPEDEZA, SERICEA (LESPEDEZA CUNEATA) SCARIFIED	60 LBS	1.4 LB	M-L P C		350,000 SEED PER POUND. WIDELY ADAPTED. LOW MAINTENANCE. MIX WITH WEEPING LOVEGRASS, COMMON BERMUDA, BAHIA, OR TALL FESCUE. TAKES 2 TO 3 YEARS TO BECOME FULLY ESTABLISHED. EXCELLENT ON ROAD BANKS. INOCULATE SEED WITH EL INOCULANT.	
UNSCARIFIED	75 LBS	1.7 LB	M-L P C		MIX WITH TALL FESCUE OR WINTER ANNUALS.	
SEED-BEARING HAY	3 TONS	138 LB	M-L P C		CUT WHEN SEED IS MATURE. BUT BEFORE IT SHATTERS. TALL FESCUE OR WINTER ANNUALS.	
LOVEGRASS, WEEPING (ERAGROSTIS CURVULA)			M-L P		1,500,000 SEED PER POUND. QUICK COVER. DROUGHT TOLERANT. GROWS WELL WITH SERICEA LESPEDEZA	
ALONE	4 LBS	0.1 LB			UN KUADBANKS.	
WITH OTHER PERENNIALS	2 LBS	0.05 LB				

**#**52 DISTURBED AREA STABILIZATION WITH MULCHING, TEMPORARY SEEDINGS AND PERMANENT SEEDINGS Ds2 Ds1 SCALE: NTS DATE:1/24/04

		INTEGRATED         Science &         Bugineering         1039 SULLIVAN ROAD, SUITE 200, NEWNAN, GEORGIA 30265         (P) 678.552.2106         (P) 678.552.2107         COA NO. PEF0006251
		REGISTERED WINTERSTURIED WINTERSTURIED WINTERSTURIED WINTERSTURIED WINTERSTURIED
		by:         Check by:         8
)		Date:     Drawn       4/11/24     MGW       Project #:     Design       1521.2201     DLO
S		CONSTRUCTION PLANS FOR SYLVANIA WPCP UPGRADES LOCATED IN SCREVEN COUNTY, GEORGIA
		ESPC DETAILS
	#2 DAVIS L. OZIER, P.E. GA PE #: 048259 GSWCC LEVEL II#: 77764	drawing no.

![](_page_27_Figure_0.jpeg)

![](_page_28_Figure_0.jpeg)

![](_page_29_Figure_0.jpeg)

![](_page_29_Figure_2.jpeg)

![](_page_29_Figure_3.jpeg)

![](_page_29_Figure_4.jpeg)

![](_page_30_Figure_0.jpeg)

INTEGRA	Science &	Fnøineerin			1039 SULLIVAN ROAD, SUITE 200, NEWNAN, GEOF	(P) 678.552.2106   (F) 678.552.2107 COA No. PEF000625   Exp. 06/30/2024
C L O R G C L SEGISTERED V REGISTERED V NO. FEOLOWING NO. FEOL						
					4	e Apr.
8	6	4	3	2 2	1 ISSUED FOR BID 4/12/2	Rev. Description Dat
Date:Drawn by:Check by:4/11/24MGWDLO	Project #: Design by: Review by: 1521.2201 DLO DLO			SCALE: AS SHOWN		
CONSTRUCTION PLANS	FOR		DILVANIA WFUT UTUNAUED			LOCATED IN SCREVEN COUNTY, GEORGIA
MISCELLANEOUS CIVIL DETAILS						
drawing no. C702						

![](_page_31_Figure_0.jpeg)

![](_page_31_Figure_5.jpeg)

![](_page_31_Figure_6.jpeg)

0 H N M 4 Ω Ω H

INTEGRATEI Science ぐ Engineering

![](_page_32_Figure_0.jpeg)

![](_page_32_Figure_1.jpeg)

NOTE: 1. PUMPS, MOUNTING HARDWARE, GUIDE RILS & SUPPORT BRACKET TO BE PROVIDED BY PASS SYSTEM MANUFACTURER. 2. ALL PIPE & FITTINGS TO BE PROVIDED BY CONTRACTOR. 3. 12" ELECTROMAGNETIC FLOW METER SHALL BE McCOMETER UM12-1SR100A1 W/ PROCOMM CONVERTER, KRHONE OPTIFLUX 2100 W/ IFC 100 CONVERTOR, OR APPROVED EQUAL. 4. 4" ELECTROMAGNETIC FLOW METER SHALL BE McCROMETER UM04-1SR100A1 W/ PROCOMM CONVERTOR, KROHNE OPTIELUX 2100 W/ IFC 100 CONVERTOR, OR APPROVED EQUAL	SYLVANI
IFC 100 CONVERTOR, OR APPROVED EQUAL	STAGED REACTOR MECHANICAL SECTIONS
	drawing no.

VALVE SCHEDULE					
DESCRIPTION	OPERATOR	SPECIFICATION			
12" CHECK VALVE (FL/FL)	AUTOMATIC W/ VISUSAL POSITION INDICATOR	40 05 51 2.02			
4" FLAP VALVE (FL)	AUTOMATIC	40 05 51 2.03			
4" FLAP VALVE (FL)	AUTOMATIC	40 05 51 2.03			
4" FLAP VALVE (FL)	AUTOMATIC	40 05 51 2.03			
2" COMBINATION AIR VALVE (SADDLE)	AUTOMATIC	40 05 51 2.07			

![](_page_32_Picture_4.jpeg)

∽ 10" DIP

1

∖ M-200 /

T.O.W. 173.5

SECTION

<u>___</u>

SS GUIDE RAIL

- INTERMEDIATE SUPPORT BRACKET

- 3" X 4" DIP REDUCER (FL/FL)

- SS LIFTING CHAIN

~ 2.4 HP WAS PUMP

TOS 155.5

(TYP 2)

INTEGRATED Science ぐ Engineering

8 6 6 7 7 8 7 8

SCALE: AS SHOWN

 $\boldsymbol{\mathcal{N}}$ 

ADE

UPGR

d

WPCI

NS

CONSTRUCTION PL. FOR

Drawn by: Chec MGW DLO Design by: Revie DLO DLO

/24 set #: 2201

![](_page_33_Figure_0.jpeg)

![](_page_34_Picture_0.jpeg)

![](_page_34_Picture_1.jpeg)

![](_page_34_Picture_2.jpeg)

![](_page_35_Figure_0.jpeg)


IDENTIFIER	DESCRIPTION	OPERATOR	SPECIFICATION
SL-TV-1	8" TELESCOPING VALVE (FL)	RACK & PINION W/ HAND WHEEL	40 05 51 2.06
SL-TV-2	8" TELESCOPING VALVE (FL)	RACK & PINION W/ HAND WHEEL	40 05 51 2.06
SL-TV-3	8" TELESCOPING VALVE (FL)	RACK & PINION W/ HAND WHEEL	40 05 51 2.06

12" DIP FROM

AERATION BASINS

→

ALSO PROVIDE A MIN OF 1 FULL JOINT OF RJ DIP ON ALL SIDES OF FITTINGS BY USE OF

- 2. PROVIDE 4" X 4" X ³/₈" SS ANGLE WITH 4" LENGTH FOR CONNECTING PRECAST RISER TO BOTTOM SLAB. ATTACH ANGLE THROUGH ONE ¹/₂" Ø HOLE IN EACH LEG USING SS 4" X ⁷/₁₆" WEDGE ANCHOR,
- 3. FIELD VERIFY ELEVATIONS AND PROVIDE CORED HOLES FOR CONNECTING PIPES INTO STRC. PROVIDE APPROPRIATELY SIZED KOR-N-SEAL BOOT FOR PIPE CONNECTION.

12" DIP





VALVE SCHEDULE							
IDENTIFIER	DESCRIPTION	OPERATOR	SPECIFICATION				
FIL-BFV-1	16" BUTTERFLY VALVE (FL)	WORM GEAR W/ HAND WHEEL AND EXTENSION ASSEMBLY, N.O.	40 05 51 2.05				
FIL-BFV-2	16" BUTTERFLY VALVE (FL)	WORM GEAR W/ HAND WHEEL AND EXTENSION ASSEMBLY, N.O.	40 05 51 2.05				
TD-PV-1	6" PLUG VALVE (MJ/MJ)	DIRECT NUT, N.C.	40 05 51 2.04				
TD-PV-2	6" PLUG VALVE (MJ/MJ)	DIRECT NUT, N.C.	40 05 51 2.04				

- 4) ALL PIPE SHALL BE PC 350 DIP UNLESS OTHERWISE NOTED. C900 PVC MAY BE SUBSTITUTED FOR THE 10" DIP OVERFLOW TO THE RAS PS AND FOR INFLUENT AND EFFLUENT PIPING. SEE CONTRACT DOCUMENTS

M106













**PUMP STATION NOTES:** 

- 1. THE DESIGN AND LAYOUT OF THIS SUBMERSIBLE LIFT STATION IS BASED ON SUBMERSIBLE PUMPS MANUFACTURED BY HAYWARD GORDON OR VAUGHAN. IF AN ALTERNATE SUBMERSIBLE PUMP IS PROPOSED, THE CONTRACTOR SHALL BEAR THE COST OF REDESIGN AND RESUBMITTAL REQUIRED BY AN ALTERNATE
- 2. THE CONTRACTOR SHALL SUPPLY THE FOLLOWING SPARE PARTS TO THE OWNER: 1 - SET UPPER & LOWER SEALS 1 - SET UPPER & LOWER BEARINGS
- REPRESENTATIVE FOR PROPER ROTATION, PUMPING CAPACITY, AMPERAGE DRAW, LACK OF VIBRATION, AND OTHER CHECKS AS MAY BE DEEMED NECESSARY TO ASSURE PROPER OPERATION. ALL SUBMERSIBLE PUMPS SHALL BE PULLED OUT OF AND REINSTALLED IN THE WET WELL IN THE PRESENCE OF A REPRESENTATIVE OWNER TO ASSURE PROPER CLEARANCES FOR EASY REMOVAL OF THE PUMPS FOR MAINTENANCE.
- 4. THE AREA SURROUNDING THE LIFT STATION SHALL BE GRADED TO PROVIDE A MINIMUM OF 0.5% SLOPE AWAY FROM THE STATION IN ALL DIRECTIONS.
- 5. THE CONTRACTOR SHALL PROVIDE <u>ALL</u> NECESSARY PIPING, VALVES, FITTINGS, EQUIPMENT, AND ELECTRICAL FOR A COMPLETELY OPERABLE LIFT STATION AS REQUIRED BY THESE PLANS AND REFERENCED SPECIFICATIONS.
- 6. ALL UNIFLANGE JOINTS ARE TO BE SECURED WITH THREADED ROD TO THE NEAREST FLANGED OR MECHANICAL JOINT FITTINGS.

VALVE SCHEDULE						
IDENTIFIER	IDENTIFIER DESCRIPTION OPERAT		SPECIFICATION			
RAS-PV-1	8" PLUG VALVE (FL/FL)	WORM GEAR AND HAND WHEEL, N.O.	40 05 51 2.04			
RAS-PV-2	8" PLUG VALVE (FL/FL)	WORM GEAR AND HAND WHEEL, N.O.	40 05 51 2.04			
RAS-PV-3	8" PLUG VALVE (FL/FL)	WORM GEAR AND HAND WHEEL, N.O.	40 05 51 2.04			
RAS-PV-4	8" PLUG VALVE (MJ/MJ)	DIRECT NUT, N.O.	40 05 51 2.04			
RAS-PV-5	8" PLUG VALVE (MJ/MJ)	DIRECT NUT, N.C.	40 05 51 2.04			
RAS-PV-6	8" PLUG VALVE (MJ/MJ)	DIRECT NUT, N.O.	40 05 51 2.04			
RAS-CV-1	8" CHECK VALVE (FL/FL)	AUTOMATIC W/ VISUSAL POSITION INDICATOR	40 05 51 2.02			
RAS-CV-2	8" CHECK VALVE (FL/FL)	AUTOMATIC W/ VISUSAL POSITION INDICATOR	40 05 51 2.02			
RAS-CV-3	8" CHECK VALVE (FL/FL)	AUTOMATIC W/ VISUSAL POSITION INDICATOR	40 05 51 2.02			
RAS-CV-4	8" CHECK VALVE (FL/FL)	AUTOMATIC W/ VISUSAL POSITION INDICATOR	40 05 51 2.02			



	SIKUCIUKE AND EQUIPMENT SCHEDULE:
Α.	WETWELL BASE. DESIGN IS A SIMPLE PRECAST BASE SECTION WITH BASE SLAB.
	FLOATATION TO BE PREVENTED VIA A CAST IN PLACE ANTI-FLOATATION RING.
	RING SHALL BE 12" THICK. WIDTH SHALL BE AS SHOWN ON DRAWING. RING SHALL
	BE CONNECTED TO THE BASE WITH 18" LONG #5 REBAR. CONTRACTOR TO DRILL
	AND PLACE REBAR INTO PRECAST BASE WITH EPOXY @ THE FOLLOWING
	LOCATIONS; 0°, 30°, 60°, 90°, 120°, 150°, 180°, 210°, 240°, 270°, 300°, 330°, AND 360°
	FOR A TOTAL OF 12 LOCATIONS. 9" OF THE REBAR TO BE EMBEDDED INTO BASE
	WITH REMAINING 9" CAST INTO THE CONCRETE COLLAR. PRE-CAST
	ANTI-FLOATATION COLLAR MAY BE USED WITH APPROVAL BY ENGINEER
В.	8' DIAMETER WETWELL RISER. COAT ALL INTERIOR WETWELL SURFACES WITH 20
	MIL OF COAL TAR EPOXY. BUTYL SEALANT @ ALL JOINTS. PIPE BOOTS FOR ALL
	PIPE PENETRATIONS.
C.	PRECAST TOP W/ HATCH AND VENT SIZE SHOWN OR 12" THICK CAST IN PLACE TOP
	W/ #5'S @12" O.C.; E.W.; E.F.
D.	60° CAST IN PLACE CONCRETE BENCH
E.	7'-6" x 8'-0" PRECAST CONCRETE VAULT. VAULT TO HAVE BOTTOM W/ GROUT
	TOWARDS DRAIN
F.	4" PVC VAULT DRAIN W/ P-TRAP. GROUT ALL PENETRATIONS. FILL P-TRAP WITH
	WATER
G	CONTRACTOR SHALL HAVE GEOTECHNICAL ENGINEER EVALUATE SOILS TO
0.	VERIEV A MINIMUM BEARING CAPACITY OF 2000 LB/SOFT JE NOT CONTRACTOR
	SHALL INCORPORATE RECOMMENDATIONS OF GEOTECHNICAL ENGINEER AT NO
	COST TO OWNER
н	6" #57 STONE
	BACKELL WETWELL AND VALVE VALUET IN 24" LIETS TO 95% STANDARD PROCTOR
··	ALLIMINUM HATCH W/ SAFETY GRATE HATCH SHALL BE SIZED TO ALLOW A 36" x 78
0.	CLEAR OPENING AND SHALL BE CENTERED OVER THE PLIMPS, SEE DETAIL
ĸ	ALLIMINUM HATCH W/ SAFETY GRATE HATCH SHALL BE SIZED TO ALLOW A 36" x 78
ι.	CLEAR OPENING AND SHALL BE CENTERED OVER VALVES. SEE DETAIL
1	LIDDER AND INTERMEDIATE CLUDE RAIL RRACKETS TWO INTERMEDIATE RRACKETS
с.	
	REQUIRED FER FOMF. CONTRACTOR TO ALSO SUFFET GUIDE RAILS. ALL TO BE
Ν.4	CARLE ASSEMBLY WITH ODD EVE DUMD DEMOVAL SVSTEM ALL STAINT FOR STEL
IVI.	
IN.	LEVEL TRANSMITTED TO INCLUDE SUSPENSION CADLE, CADLE MANOED LISTING
	LEVEL TRANSMITTER. TO INCLUDE SUSPENSION CABLE, CABLE HANGER, LIFTING
0.	
Ρ.	
Q.	TWO PUMP SELECTIONS FOR PUMP DUTY POINT OF 1048 GPM @ 39.0 TDH OF
	1. HAYWARD GORDON CHOPX5B-S W/ 9.125" IMPELLER 460 V, 3 PH, 60 HZ, 25 HP
	2. VAUGHAN SE6U W/ 10.9" IMPELLER 460 V, 3 PH, 60 HZ, 20 HP
R.	ELECTROMAGNETIC FLOW METER. SIGNAL CONVERTOR TO BE LOCATED WITH
	PUMP CONTROL PANEL.
	1. McCROMETER UM08-1SR025A1 WITH PROCOMM CONVERTOR
	2. KROHNE OPTIFLUX 2100 WITH IFC 100 CONVERTOR
S.	DAVIT CRANE: THERN 5FT25-M2 OR APPROVED EQUAL WITH 2,800 LB LIFTING
	CAPACITY, WORM GEAR HAND WINCH, AND 36' OF STAINLESS STEEL WIRE ROPE.







	VALVE SCHEDULE								
IDENTIFIER	DESCRIPTION	OPERATOR							
WAS-PV-2	3" PLUG VALVE (MJ/MJ)	DIRECT NUT, N.O.							
WAS-PV-3	6" PLUG VALVE (MJ/MJ)	DIRECT NUT, N.C.							
WAS-TV-1	6" TELESCOPING VALVE	RACK & PINION W/ HAND WHEEL							
WAS-TV-2	6" TELESCOPING VALVE	RACK & PINION W/ HAND WHEEL							

SPECIFICATION
40 05 51 2.04
40 05 51 2.04
40 05 51 2.06
40 05 51 2.06















	1039 SULLIVAN ROAD, SUITE 200, NEWNAN, GEORGIA 30265         1030 SULLIVAN ROAD, SUITE 200, NEWNAN, GEORGIA 30265							
		10 × × × × ×	0 62	R IST CEESIVENIS	GRE	しいいませいど	~)~	*)
							4/12/24	Date Apr.
8	7	9	5	4	3	2	1 ISSUED FOR BID	Rev. Description
Date: Drawn by: Check by:	4/11/24 MGW DLO	Project #: Design by: Review by:	1521.2201 DLO DLO			SCALE: AS SHOWN		
	CONSTRUCTION PLANS FOR SYLVANIA WPCP UPGRADES Located in Screven county, georgia							
	AEROBIC DIGESTER SECTIONS & DETAILS							
ſ	D	R/	\w M	'IN 1	с 1	∾ 1	0.	

-1/2" ADHESIVE  $\begin{pmatrix} 6 \\ M-203 \end{pmatrix}$ LEVEL MOUNTING -SURFACE W/ GROUT

 2
 MOORING POST ANCHOR DETAIL

 M-111
 SCALE: N.T.S.



NOTE 1. FLOATING MIXER TO BE MOUNTED IN SAME MANNER. MIXER ASSEMBLY DOES NOT REQUIRE FIBERGLASS DOME.



Science &	Engineering	1039 SULLIVAN ROAD, SUITE 200, NEWNAN, GEORGIA 30265	(P) 678.552.2106   (F) 678.552.2107 COA No. PEF000625   EXP. 06/30/2024			
C L L C L C L C L C L C L C L C L C L C	R G GISTERE FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO FEOLO	AND HE	*			
	1 1		apr.			
		4/12/24	Date			
		2 ISSUED FOR BID	ev. Description			
Date:Drawn by:Check by:4/11/24MGWDLOProject #:Design by:Review by:1521.2201DLO		SCALE: AS SHOWN				
CONSTRUCTION PLANS FOR	CONSTRUCTION PLANS FOR SYLVANIA WPCP UPGRADES Located in Screven county, georgia					
DEWATERING BUILDING EXISTING CONDITIONS AND DEMO PLAN						
DRAW	ving 1111	NO. 2				









POLYMER FEED SKID LAYOUT
SCALE: 1" = 1'-0"









- BUILD UP LEVEL PAD AS NEEDED W/ CONCRETE







	to a solution of the second solution of the s							
		A A A A A A A A A A A A A A A A A A A	0 20 0000	RIST	GERE	していいませいひ	V) )	*
							l2/24	Date Apr.
8	7	6	5	4	3	2 7	1 ISSUED FOR BID	Rev. Description
Date: Drawn by: Check by:	4/11/24 MGW DLO	Project #: Design by: Review by:	1521.2201 DLO DLO			SCALE: AS SHOWN		
CONCEPTION DE ANC	CONSTRUCTION PLANS FOR SYLVANIA WPCP UPGRADES Located in Screven county, georgia							
	CHEMICAL FEED SECTIONS							
	DRAWING NO. M116							

(1) CHEMICAL FEED SKID M-116) SCALE: N.T.S.

VALVE SCHEDULE						
VALVE #	POSITION					
V-1	OPEN					
V-2	CLOSED					
V-3	OPEN					
V-4	CYCLED W/ PUMP					
V-5	CYCLED W/ PUMP					
V-6	CLOSED					
V-7	CLOSED					
V-8	OPEN					
V-9	OPEN					
V-10	OPEN					
V-11	CLOSED					
V-12	OPEN					







- BOTH INSIDE AND OUTSIDE OF POST IS COATED.) 2. ANCHOR BOLT SIZE SHOWN IS MINIMUM, PROVIDE LARGER SIZE IF NECESSARY TO MEET LOAD REQUIREMENTS.
- 3. FOUR ANCHOR BOLTS REQUIRED AT BASE FLANGE MOUNT. TWO ANCHOR BOLTS/BOLTS MAY BE USED AT SIDE MOUNTS IF ANCHOR BOLT/BOLT SIZE IS 1/2" MINIMUM AND BOLT IS CENTERED IN BRACKET.
- 4. UNLESS SPECIFICALLY INDICATED OTHERWISE, GUARDRAIL MOUNTING TO CONCRETE MAY BE
- BY ANY SHOWN METHOD AS APPLICABLE 5. SHIM MATERIAL SHALL MATCH BEAM MATERIAL AND SHALL BE FULL SIZE OF GUARDRAIL
- MOUNTING BRACKET.
- 6. HOLE MAY BE CORE DRILLED AT CONTRACTOR OPTION.

HANDRAIL POST ANCHORAGE ____





1. ADJUST GUARDRAIL AS REQUIRED FOR PIPING AND GATES.

2. AT METAL STAIRS, USE SIDE MOUNT. AT CONCRETE STAIRS, USE BASE FLANGE, EMBEDDED POST OR SIDE MOUNT, EXCEPT WHERE STAIR WIDTH IS LESS THAN 4'-0". USE SIDE MOUNT ONLY. SEE GUARDRAIL POST ANCHORAGE DETAIL.

_____

HANDRAIL









ALUMINUM GRATING

SCALE: N.T.S.

M202 /

LOAD CHART FOR ALUMINUM I-BAR GRATING						
MAXIMUM SPAN		GR DI	ATING EPTH			
3'-8"		1	1/4"			
4'-2"		1	1/2"			
4'-8"		1	3/4"			
5'-2"			2"			
5'-8"		2	1/4"			
6'-2"		2	1/2"			
-	AS SF	PECIFIED	ELSEWHERE			





Science of	Engineering		1039 SULLIVAN ROAD, SUITE 200, NEWNAN, GEORGIA 30265	(p) 678.552.2106   (f) 678.552.2107 COA No. PEF000625   Exp. 06/30/2024
C L C C	REOME	一日日の日		*)
		1	24	te Apr.
			ISSUED FOR BID 4/12	v. Description D
Date:Drawn by:Check by:84/11/24MGWDLO7Project #:Design by:Review by:61521.2201DLO5		SCALE: AS SHOWN	1	Re
CONSTRUCTION PLANS FOR	SYLVANIA WPCP UPGRADES			LOCATED IN SCREVEN COUNTY, GEORGIA
MISCELLANEOUS	MECHANICAL	DETAILS		
DRAW M	ving 120	ہ 33	0.	









54'-6"	
4'-0" O	
3 3 TOW 142.00 N 144.00	
+/- 8'-0"	TOW 141.00





A CHLORINE CONTACT CHAMBER SECTION S-102 SCALE: 1/2" = 1'





BPARSHALL FLUME SECTIONS-103SCALE: 1/2" = 1'

NOTE: 1. FOLLOW MFR INSTALLATION INSTRUCTIONS FOR PARSHALL FLUME INSERT.

#4 @ 12" O/C W/ 8" HOOK, EF. -





**- -** 8"









				Science &	Engineering			1039 SULLIVAN ROAD, SUITE 200, NEWNAN, GEORGIA 30265	(P) 678.552.2106   (F) 678.552.2107 COA No. PEF0006251 EXP. 06/30/2024
			10 22 01	0 22 000	RIST	GERE	しいいませいご	~))~	*)
$\left  \right $								2/24	ate Apr.
	- 8	7 7		5	4	3	2	1 ISSUED FOR BID 4/1	Rev. Description
	Date: Drawn by: Check by:	4/11/24 MGW DLO	Project #: Design by: Review by	1521.2201 DLO DLO		2' 1' 0' 2'			SCALE: $1/2^{n} = 1^{n}$
		CUINDIAUCTION FLAIND	FOR		CVI VIANIA WIDCD I IDCD A DEC	DILVANIA WICI UTUNALED			LOCATED IN SCREVEN COUNTY, GEORGIA
				CASCADE AERATION	STRUCTURAL PLANS AND		SECTIONS		
		D	R/	S.	'IN 1(	G )4	∾ 1	0.	





ALUM ALTERNATING TREAD STAIRS -

ATTACH BY MFR PROVIDED -FLOOTPLATE

EL. 144.0 1'-0" -

(4) #4, EW

WALL SECTION 1-1'-0" _

#5 @ 12" O/C, T&B — EL. 136.5 — 4'-0" Ø CONT. 6" PVC WATERSTOP – EL.133.5 4'-0" EL. 132.5 <u>→</u> 3'-4" → 3'-4" →



S106



	CONTROL AND ONE	LINE DIAGRAMS			<u>General</u> Abb	<u>reviatic</u>	)NS
	CONDUCTORS CONNECTED CONDUCTORS NOT CONNECTED CONNECTION POINT	INTERLOCK CONTACTS 12 9 CR CR CR CR CR CR	CONTROL RELAY CONTACTS WITH NUMERIC PREFIX.	AR AS A, AMP AC AFF AHAP AIC	ALARM RELAY AMMETER SELECTOR SWITCH AMP(S), AMPERE(S) ALTERNATING CURRENT ABOVE FINISHED FLOOR AS HIGH AS POSSIBLE AMPS INTERRUPTING	M MAX MCB MCC MCP	MOTOR CONTACTOR MILLIAMPERE MAXIMUM MAIN CIRCUIT BREAKER MOTOR CONTROL CENTER MOTOR CONTROL PANEL/ MOTOR CIRCUIT PROTECTOR
XX MCP/3 100/70	TERMINAL POINT FOR OUTGOING CONDUCTORS, WITH IDENTIFICATION. "XX" DENOTES CONTRACTOR ASSIGNED. MAGNETIC-ONLY CIRCUIT BREAKER (MCP), WITH CURRENT RATING	2° To	ON DELAY (DELAY ON COIL ENERGIZATION) RELAY CONTACTS WITH NUMERIC PREFIX AND OPTIONAL REF. OR DESCRIPTION. NOTC = NORMALLY OPEN TIME CLOSE. NCTO = NORMALLY CLOSE TIME OPEN	AL AT AF AUTO AUX AWG	CAPACITY, SYMM. ALUMINUM AMPERE TRIP AMPERE FRAME AUTOMATIC AUXILIARY AMERICAN WIRE GAUGE	MECH MFR MH MIC MIN MISC mM	MECHANICAL MANUFACTURE(R) MANHOLE MICROPHONE MINIMUM MISCELLANEOUS MILLIMETER
100/30 	CIRCUIT BREAKER, THERMAL-MAGNETIC UNLESS OTHERWISE NOTED, WITH FRAME SIZE AND TRIP RATING FUSE WITH SIZE AND OPTIONAL IDENTIFICATION.		OFF DELAY (DELAY ON COIL DE-ENERGIZATION) RELAY CONTACTS WITH NUMERIC PREFIX AND OPTIONAL REF. OR DESCRIPTION. NOTO = NORMALLY OPEN TIME OPEN. NCTC = NORMALLY CLOSED TIMED CLOSED	BC BKR	BARE COPPER CONDUCTOR BREAKER	mV MCM MOP MPR MCB MTP	MILLIVOLT MILLI CIRCULAR MILLS MOTOR OPERATOR PANEL MOTOR PROTECTION RELAY MAIN CIRCUIT BREAKER
	FUSE WITH BLOWN FUSE INDICATOR.		TIME DELAY RELAY INSTANTANEOUS CONTACTS WITH NUMERIC PREFIX.	C CAP CB CKT CLG CR	CONDUCTOR/CONTACTOR CAPACITOR CIRCUIT BREAKER CIRCUIT CEILING CONTROL RELAY	MVS N/A NC NEUT,N	MOTOR MEDIUM VOLTAGE STARTER NOT APPLICABLE NORMALLY CLOSED NEUTRAL
	DISCONNECT SWITCH. RATING OPTIONAL. 30 AMP 600V MINIMUM UNLESS OTHERWISE NOTED.	$\underbrace{\overset{600AF}{600AT}}_{\longleftarrow}$	LOW VOLTAGE POWER CIRCUIT AND BREAKER DRAWOUT TYPE, FRAME TRIP SHOWN MOULDED CASE CIRCUIT BREAKER, FRAME AND TRIP ID SHOWN	CND CONC CS CONT CPT	CONDUIT CONCRETE CONTROL SWITCH CONTROL CONTROL POWER TRANSFORMER	NO NOM NP NTS	NORMALLY OPEN NOMINAL NAMEPLATE NOT TO SCALE
M	MOTOR (PHASES AS REQUIRED)	o o I	LIGHTNING ARRESTOR AND GROUND	CT CU D DB	CURRENT TRANSFORMER COPPER DIAMETER DUCT BANK	OC OD OH OL'S OS	ON CENTER OUTSIDE DIAMETER OVERHEAD OVERLOADS OCCUPANCY SENSOR
250W 	SPACE HEATER, WATTAGE AS INDICATED.	 300A	DISCONNECT OR ISOLATING SWITCH: CONTINUOUS RATING	DC DET DIAG DPSH DS	DIRECT CURRENT DETAIL DIAGRAM DIFFERENTIAL PRESSURE SWITCH DISCONNECT SWITCH	OI PA PB PE	OIL IIGHI POLE PUBLIC ADDRESS PUSHBUTTON, PULLBOX PHOTO ELECTRIC CELL
120V	CONTROL POWER TRANSFORMER, PRIMARY AND SECONDARY VOLTAGE SHOWN. SIZE AS SHOWN OR SPECIFIED.		MAGNETIC-ONLY CIRCUIT BREAKER (MCP), DRAWOUT TYPE, WITH CURRENT RATING	DWG EA EC EF	DRAWING EACH ELECTRICAL CONTRACTOR EXHAUST FAN	PF PH PLC PM	POWER FACTOR PHASE PROGRAMMABLE LOGIC CONTROLLER PHASE MONITOR
50/5	CURRENT TRANSFORMER. PRIMARY/SECONDARY TURNS RATIO SHOWN. HORN	100E 200A	FUSED SWITCH: FUSE AND SWITCH CONTINUOUS RATINGS SHOWN	EL ELEC EMER ENCL EP EQUIP FX	ELEVATION ELECTRIC(AL) EMERGENCY ENCLOSURE/ENCLOSED EXPLOSION PROOF EQUIPMENT EXISTING	PNL PP PR PRI PS PT	PANEL POWER PANEL PAIR PRIMARY PRESSURE SWITCH POTENTIAL TRANSFORMER
1250HM ₩	RESISTOR: OPTIONAL VALUE SHOWN RECTIFIER TRIAD	100KVA UUU 13.2KV 5.75% MM 480/227V	POWER TRANSFORMER: PRIMARY & SECONDARY VOLTAGES, %Z, SIZE SHOWN	FCP FDR FLA FPP FS	FURNISHED WITH EQUIPMENT PANEL FEEDER FULL LOAD AMPS FIBER OPTIC DISTRIBUTION PANEL FLOW SWITCH	PVC PWR QSH RCPT RCT	POLYVINYL CHLORIDE POWER SHEAR PIN LIMIT SWITCH RECEPTACLE REACTOR
	SURGE SUPPRESSOR CAPACITOR: OPTION VALUE SHOWN	1.5KVA U 120V 2.5% TO 240/120V	ISOLATION TRANSFORMER PRIMARY & SECONDARY VOLTAGES, %Z, SIZE SHOWN	FU FUT FVNR FVR GALV	FUSE FUTURE FULL VOLTAGE NON-REVERSING FULL VOLTAGE REVERSING GALVANIZED	REF REQD RMS RTD SCH	REFERENCE REQUIRED ROOT MEAN SQUARE RESISTANCE TEMPERATURE DETECTOR SCHEDULE
INDICATORS	$\begin{array}{llllllllllllllllllllllllllllllllllll$	4.16 KV 120 V	POTENTIAL TRANSFORMER PRIMARY & SECONDARY VOLTAGES & WINDINGS SHOWN. (x) UNITS	GEN GFR GRD GRS H HD HGT	GROUND FAULT RELAY GROUND GALVANIZED RIGID STEEL HIGH HEAT DETECTOR HEIGHT	SD SEC SEL SPDT SPEC SPHTR SPKR SS	SMOKE DETECTOR SECONDARY SELECTOR SINGLE POLE DOUBLE THROW SPECIFICATION MOTOR SPACE HEATER SPEAKER SPEED SWITCH
STATUS	PUSH TO TEST TEST VOLTAGE TERMINAL SHOWN	$250/5  \boxed{3}$	CURRENT TRANSFORMER: RATIO SHOWN (3 INDICATES NO. OF CT'S) METER SWITCH, XS:	HH HID HP HS HVAC	HANDHOLE HIGH INTENSITY DISCHARGE HORSEPOWER HAND STATION (SWITCH) HEATING, VENTILATION, AND AIR CONDITIONING	SUB SW SYMM SYS SV SPB	SUBSTATION SWITCH SYMMETRICAL SYSTEM SOLENOID OPERATED VALVE SIGNAL PULL BOX
C – C – DESCPTN COILS:	REMOTE TEST TEST BUS TERMINAL SHOWN	xS	AS – AMMETER SWITCH VS – VOLTMERE SWITCH FS – FREQUENCY SWITCH METER:	HZ HOA HMH ID	HERTZ (CYCLES PER SECOND) HAND/OFF/AUTO HIGH VOLTAGE MANHOLE INSIDE DIAMETER	TCB TB TEL TEMP	TERMINAL CABINET TERMINAL BOX TELEPHONE TEMPERATURE
SHUNT:	<ul> <li>a) CONTACTOR COILS WITH OPTIONAL DESCRIPTION OR REF. EXAMPLE: CONTACTOR COIL FOR LTG CKT #1</li> <li>C = CONTACTOR, LIGHTING OR GENERAL USE</li> <li>F = FAST OR FORWARD</li> <li>M = MAIN OR LINE</li> <li>MO = MOTOR OPERATOR</li> </ul>	$(3)^{0-1000}$	A – AMMETER W – WATTMETER KWH – WATT–HOUR METER F – FREQUENCY METER VAR – VAR METER V – VOLTMETER	IMC INTLK INST INSTR I/O JB	INDIVIDUAL MOTOR CONTROLLER INTERLOCK INSTANTANEOUS INSTRUMENT INPUT-OUTPUT JUNCTION BOX	TH TJB TSH TV TYP TR TVSS	THERMOSTAT TERMINAL JUNCTION BOX TEMPERATURE SWITCH HIGH TELEVISION TYPICAL TIMING RELAY TRANSIENT, VOLTAGE, SURGE, SUPPRESSOR
	2M = SECOND MAIN OR DELTA R = RUN OR REVERSE S = SLOW OR START KIC = TIME CONTROLLER b) RELAY COILS WITH NUMERIC PREFIX AND OPTIONAL		ANSI C37.2 DEVICE WINDING CONFIGURATION: PER ANSI DELTA	KV KVA KVAR KW KWH	KILOVOLT KILOVOLT-AMPERE KILOVOLT-AMPERE REACTIVE KILOWATT KILOWATT-HOUR	TSP UG UH UON V	TWISTED SHIELDED PAIR UNDERGROUND UNIT HEATER UNLESS OTHERWISE NOTED VOLT
AUTO ENABLE	DESCRIPTION OR REF. EXAMPLE: CONTROL RELAY 10 USED AS AUTO ENABLE. CR = CONTROL RELAY U = UNLATCH L = LATCH	↓ 50AMP/10SEC	WYE (GROUNDED) NEUTRAL GROUNDING RESISTOR:	L-O-R L LC LCS	LOCAL-OFF-REMOTE LONG LIGHTING CONTACTOR LOCAL CONTROL STATION	VA VAR VFD VSH W	VOLT AMPERE VOLT AMPERE REACTIVE VARIABLE FREQUENCY DRIVE VIBRATION SWITCH WATT, WIRE, WIDE
ON or OFF DELAY RANGE × TO ×× SEC/M SET AT × SEC/MIN	<ul> <li>c) TIME DELAY COIL WITH NUMERIC PREFIX, DELAY ACTION, AND OPTIONAL TIMING RANGE AND SETTING. EXAMPLE: TIME DELAY RELAY 9TR.</li> <li>TR = TIMING RELAY</li> </ul>	Ļ	AMPS/TIME RATING SHOWN	LP LOS LSL LSO LSC LTG	LIGHTING PANEL LOCK-OUT STOP LEVEL SWITCH LOW LIMIT SWITCH OPEN LIMIT SWITCH CLOSED LIGHTING	W/ W/O WP WSH ZS	WITH WITHOUT WEATHERPROOF OVERLOAD TORQUE SWITCH POSITION (LIMIT) SWITCH
	RELAY COIL WITH OPTIONAL PREFIX. OL = THERMAL OVERLOAD RELAY		I/A OR PLC ANALOG INPUT OR OUTPUT	L V LSH	LOW VOLTAGE LEVEL SWITCH HIGH	ZSH ZSL	POSITION (LIMIT) SWITCH OPEN POSITION (LIMIT) SWITCH CLOSED
	METER WITH ALPHA IDENTIFIERS: ETM = ELAPSED TIME METER		FULL VOLTAGE, NON-REVERSING MAGNETIC MOTOR STARTER. NEMA SIZE INDICATED	TYPE	SYMBOL     DESCRIPTION       10 FT. STANCHION MOUNT, 10       FIXTURE RATED FOR WET LO       POLYCARBONATE LENS	),935 LUMENS CATIONS,	IGHTING FIXTURE SCHED         MANUFACTURER         LED       CROUSE HINDS         CAT#PVM-11L-J-R1-UNV1-S890-S903-         D2S20 (NO PHOTOCELL). DARK BRONZE.
				В	LED AREA LIGHT MOUNTED C STRAIGHT ALUMINUM POLE	ON 25 FT. SQU	FIXTURE: CAT#CREE ARE-EDG-4MP-XX-06-E-UL-XX-700-40K-XX (BXALx806E-UD7) WITH INTEGRAL PHOT POLE:CAT#LYTE POLE 105-6025-25 W/ 12 SQUARE BASE PLATE





		SINGLE PHASE 15VA	MIN-F	POWE	R ZO	NE SO	CHEDULE "PANEL-LA"		
PR	IMARY-6	60A SECONDARY-80A	120/2	2 <mark>40V</mark> .,	, 1PH.	3W.	AIC, MAINS & CB'S	S-10,000	
	LOCATIO	ON - AER. BASINS		10k	(VA		NEMA 4X ENCLC	SURE	
CKT	TRIP	DESCRIPTION	CO	NNEC	TED k	۲V	DESCRIPTION	TRIP	CKT
NO.	POLES	OF LOADS	PHA	SE A	PHA	SE C	OF LOADS	POLES	NO.
1	20/1	LIGHTS	0.5	I			DIG. 1 LGT/RECEPT	20/1	2
3	20/1	RECEPTS			1.5	-	DIG. 2 LGT/RECEPT	20/1	4
5	20/1	RECEPTS	0.2	-			SPARE	20/1	6
7	20/1	RECEPTS			0.5	-	SPARE	20/1	8
9	20/1	RECEPTS	0.3	-			SPARE	20/1	10
11	20/1	SPARE			1.1	-	SPARE	20/1	12
13	20/1	SAPRE	0.1	I			SPARE	20/1	14
15	20/1	SPARE			0.1	-	SPARE	20/1	16
17	20/1	SPARE	0.5	-			SPARE	20/1	18
19	20/1	SPARE				-	SPARE	20/1	20
21	20/1	SPARE	-	-			SPARE	20/1	22
			1.0	0.0	2.0	0.0			
		TOTAL LOAD	1	.0	2	.0	3.0	KVA	
							16.7	AMPS	

### NOTES:

- 1. INSTALL THE FOLLOWING NEW CIRCUIT BREAKERS IN EXISTING 120/240V PANEL DP: A) 300A, 240V, 3P = RAS PUMP STATION CONTROL PANEL B) 60A, 240V, 3P = FILTER 1 AQUA DISK CONTROL PANEL C) 60A, 240V, 3P = FILTER 2 AQUA DISK CONTROL PANEL
  - D) 4 20A, 120V, 1P = LIGHTS AND RECEPTACLES

NEW BREAKERS SHALL BE OF THE SAME MANUFACTURER AND HAVE THE SAME AIC RATING AS THE EXISTING BREAKERS. PROVIDE NEW UPDATED TYPE WRITTEN LEGEND.

- 2. THE SURGE PROTECTION DEVICE (SPD) SHALL BE IN A NEMA 4X STAINLESS STEEL ENCLOSURE. THE SPD SHALL BE UL LISTED AND LABELED UNDER UL1449 AND UL1283, HAVE AN INTEGRAL DISCONNECT, AND HAVE A SURGE RATING OF 160KA PER PHASE. PROVIDE EATON PTE160-3Y201-SD-SS-D OR APPROVED EQUAL.
- 3. THE CONTRACTOR SHALL FURNISH AND INSTALL A COMPLETE GROUND SYSTEM CONSISTING OF A GROUND TRIANGLE WITH #2/0 BARE COPPER GROUND CONDUCTOR, 3 - 3/4" DIAMETER 10' GROUND RODS, AND CADWELD CONNECTIONS TO GROUND RODS.
- 4. PANEL LA SHALL BE A COMBINATION MINI-POWER ZONE / PANELBOARD RATED 480-120/240V, 1 PHASE, 15kVA WITH BOLT ON BREAKERS AND A STAINLESS STEEL ENCLOSURE. SEE SCHEDULE, THIS SHEET, FOR BRANCH BREAKERS.
- 5. CONTRACTOR SHALL REMOVE EXISTING AERATOR CONTROL PANEL AND DELIVER TO OWNER'S STORAGE FACILITY. CONTRACTOR SHALL DEMOLISH ALL ASSOCIATED CONDUIT AND CABLE AND REMOVE ALL EXISTING CONDUCTORS.





**ESAD, LLC** 885 WOODSTOCK ROAD SUITE 430-231 ROSWELL, GA 30075 PH: 678-469-5196

ESAD PROJECT #22026







<u>DB-10</u> 1-1" PVC (240V TO DISK 1 C.P.) 2-1" PVC (240V TO DISK 2 C.P.) 3-1" PVC (120V) 4-2.5" PVC (240V RAS PUMP C.P.) 5-1" PVC (120V) 6-1" PVC (SPARE)



DB-11 1-2.5" PVC (240V TO RAS PUMP C.P.) 2-1" PVC (120V) 2-1" PVC (SPARE)



<u>DB-12</u> 1-1" PVC (240V TO DISK 1 C.P.) 2-1" PVC (240V TO DISK 2 C.P.) 3-1" PVC (120V)



**ESAD, LLC** 885 WOODSTOCK ROAD SUITE 430-231 ROSWELL, GA 30075 PH: 678-469-5196





STAGED REACTOR PLAN VIEW

SCALE: 1/4" = 1'-0"

NOTES:

- FURNISH AND INSTALL TWO STAINLESS STEEL, NEMA 4X PULL BOXES. ONE BOX SHALL BE FOR POWER AND CONTROLS. THE SECOND BOX SHALL BE FOR #16 TSP CABLES. SIZE PER NEC. INSTALL SO BOX IS MINIMUM OF 12" ABOVE GRADE.
- 2. ROUTE 3 #8 IN  $\frac{3}{4}$ " CONDUIT BETWEEN LIGHT FIXTURES, SWITCH, AND RECEPTACLES. HOMERUN FROM BOX TO PANEL LA WITH 4 #8 IN 1"C.



# <u>DB-3</u>

1-1" PVC (480V MXRAA)
2-1" PVC (480V MXRPA)
3-1" PVC (480V PAP1)
4-1" PVC (480V PAP2)
5-1" PVC (480V PAP3)
6-1" PVC (480V WAS)
7-1" PVC (CONTROLS)
8-1" PVC (SPARE)



## <u>DB-6</u>

1-1" RGS (#16 TSP) 2-1" PVC (SPARE)

	<b>INTEGRATED</b>		Science &	Fnøineering		1039 Sullivan Road, Suite 200, Newnan, Georgia 30265	(p)o78.552.2106 (1)o78.552.2107 Atlanta/Savannah	COA #: PEF000625 Exp. 6/30/2022
		A Des P	NOF NO	D.38 ES: M.	DOBO SION	A A	A A A	*
-			-		-			e Apr.
								Description
Date: Drawn by: Check by: 8	TBD AP DMZ 7	Project #: Design by: Review by: 6	1521.2201 DMZ DLO 5	4	3	SCALE: AS SHOWN	1	Rev
	CONSTRUCTION FLANS	FOR			DILVANIA WFUT UTUNAUED			LOCATED IN LAND LOT ??? OF THE 1ST DISTRICT, SCREVEN COUNTY, GEORGIA
				STAGE REACTOR	ELECTRICAL DI AN	ELECINICAL FLAIN		
	D	R <i>A</i>	A M E	/IN <b>1</b> (	IG 0!	м 5	0.	



ESAD, LLC 885 WOODSTOCK ROAD SUITE 430-231 ROSWELL, GA 30075 PH: 678-469-5196



DISC FILTER PLAN VIEW

SCALE: 3/8" = 1'

FILTER 1 BACKWASH VALVE 1	
FILTER 1 BACKWASH VALVE 2	
FILTER 1 BACKWASH VALVE 3	
FILTER 1 BACKWASH VALVE 4	
FILTER 1 WASTE VALVE	

	_
FILTER 2 BACKWASH VALVE 1	
FILTER 2 BACKWASH VALVE 2	
FILTER 2 BACKWASH VALVE 3	
FILTER 2 BACKWASH VALVE 4	— — 7 #14 & 1 — #14 GND IN 3/4" C.
FILTER 2 WASTE VALVE	—— 7 #14 & 1 —— #14 GND IN 3/4" C.

### NOTES:

- 1. ROUTE 4 #8G IN 3/4" CONDUIT TO EACH LIGHT FIXTURE AND RECEPTACLE. HOME RUN 4 #8G IN 1"C TO PANEL DP.
- 3. INSTALL THE FILTER 1 AND FILTER 2 CONTROL PANELS ON A CONCRETE HOUSE KEEPING PAD. INSTALL ON COMMON RACK. SEE DUAL SUPPORT STAND DETAIL A / E114.



No.38080 PROFESSIONA

Rev 4 5 0 7 8

AS

ننا

Check DMZ Review DLO

ې وې

Dra AP Des DMZ

Date: TBD Projec 1521.

;#: 01

UPGRADES

WPCP

SYLVANIA

AN

DISC FILTER ELECTRICAL PLA

CONSTRUCTION PLANS FOR



## DISC FILTER #1

SCHEMATICS









DRAWING NO. E106



RAS PUMP STATION ELECTRICAL PLAN SCALE: 1/2" = 1'-0"

### NOTES:

- 1. INSTALL TYPE B LIGHT AREA LIGHT FIXTURE. FIELD LOCATE EXACT LOCATION.
- 2. ROUTE 4 #8G IN 3/4" CONDUIT TO EACH LIGHT FIXTURE AND RECEPTACLE. HOME RUN 4 #8G IN 1"C TO PANEL DP.
- INSTALL THE RAS PUMP CONTROL PANEL ON A CONCRETE HOUSE KEEPING PAD. SEE DUAL SUPPORT STAND DETAIL A / E114.





ESAD PROJECT #22026





INFLUENT FLOW METER AT PARSHALL FLUME SCHEMATIC



CHLORINE CONTACT CHAMBER - ELECTRICAL PLAN ____

SCALE: 1/4" = 1'-0"





DE-WATERING BUILDING - ELECTRICAL PLAN

SCALE: 1/4" = 1'-0"

NOTES:

- 1. ROUTE 3 #8 IN 3/4" C. TO LIGHT FIXTURE AND HOMERUN TO
- SHALL INSTALL ALL EQUIPMENT FOR DIGESTER 1 INCLUDING
- 4. CONTRACTOR SHALL RE-WIRE EXISTING DIGESTER 1 AERATOR
- 5. INSTALL DIGESTER CONTROL PANEL ON UTILITY RACK. INSTALL A 120V,20A/1P WP, GFI RECEPTACLE ADJACENT TO CIRCUIT TO

INTEGRATED Science & Engineering 0.38080 PROFESSION <u>R</u> 1 2 3 4 2 9 7 8 Chec DMZ Revie n d o Date: TBD Proje( 1521 UPGRADES ANS CONSTRUCTION PL FOR WPCP SYLVANIA AEROBIC DIGESTER 2 ELECTRICAL PLAN DRAWING NO. E109



ESAD PROJECT #22026





FIGURE E110.1



 $\frac{BELT\ PRESS}{\text{SCHEMATICS}}$ 



1. CONTRACTOR SHALL PROVIDE ALL INTERCONNECTING WIRING AND CONDUIT PER BELT PRESS SHOP DRAWINGS.

ESAD PROJECT #22026



**ESAD, LLC** 885 WOODSTOCK ROAD SUITE 430-231 ROSWELL, GA 30075 PH: 678-469-5196

DRAWING NO. E110

CONSTRUCTION PLANS FOR FOR FOR FOR FOR FOR FOR FOR FOR FOR
CONSTRUCTION PLANS FOR     CONSTRUCTION PLANS       FOR     For     Drawn by:     Check by:     B
CONSTRUCTION PLANS FOR     Date:     Drawn by:     Check by:     B
CONSTRUCTION PLANS FOR     Date:     Drawn by:     Check by:     B        FOR     FOR     AP     DMZ     7        Project #:     Design by:     Review by:     6        SYLVANIA WPCP UPGRADES     1521.2201 DMZ     0     4        SYLVANIA WPCP UPGRADES     SCALE: AS SHOWN     2
CONSTRUCTION PLANS         CONSTRUCTION PLANS         FOR         FOR         FOR         FOR         FOR         SYLVANIA WPCP UPGRADES         SCALE: AS SHOWN         LOCATED IN LAND LOT ??? OF THE 1ST DISTRICT, SCREVEN COUNTY, GEORGIA
CONSTRUCTION PLANS FOR SYLVANIA WPCP UPGRADES Located in land lot ??? OF THE 1ST DISTRICT, SCREVEN COUNTY, GEORGIA



- 1. CONTRACTOR SHALL INTERLOCK EXISTING SEWAGE PUMPS 1, 2, AND 3 WITH NEW MAGNESIUM METERING PUMPS SUCH THAT ONE METERING PUMP STARTS AND STOPS WITH ANY OF THE THREE EXISTING SEWAGE
- 2. CONTRACTOR SHALL MODIFY EXISTING MCC SUCH THAT THE FOLLOWING SIGNALS ARE MADE AVAILABLE TO
- 3. INSTALL SCADA INFLUENT ON WALL AND ROUTE 3 #12IN 3/4" C. TO EXISTING 120V PANEL 120V POWER, ROUTE 12 #14 IN 3/4" C. TO MCC, ROUTE #16 TSP IN 3/4" C. TO LEVEL CONTROL PANEL AND SPLIT

FIGURE E111.1



ESAD PROJECT #22026



AQUA-PASS

CONTROL PANEL

LCP-AP

(BY AQUA)

NOTES: 1. CONTRACTOR SHALL LABEL ALL CONDUCTORS PER THE AQUA SHOP DRAWINGS.






I. CONTRACTOR SHALL FURNISH A LOCAL SURGE SUPPRESS FOR ALL 4-WIRE FIELD MOUNTED TRANSMITTERS INCLUDING THE EFFLUENT PARSHALL FLUME, AERATION BASIN 1, 2, 3 DO PROBES, AND THE RAS FLOW METER. 2. SURGE SUPPRESSOR SHALL BE WEIDMULLER FISA FIELD INSTRUMENT IN A NEMA 4X POLYCARBONATE ENCLOSURE OR APPROVED EQUAL. 3. MOUNT SUPPRESSOR ON RACK ADJACENT TO TRANSMITTER.

> LOCAL SURGE SUPPRESSOR SCHEMATIC





IS RESPONSIBLE FOR FULLY SECURING FIXTURE SUCH THAT IT DOESN'T SWAY.

TYPE A LIGHT FIXTURE MOUNTED TO HANDRAIL DETAIL SCHEMATIC





**ESAD, LLC** 885 WOODSTOCK ROAD SUITE 430-231 ROSWELL, GA 30075 PH: 678-469-5196

DRAWING NO. E113





SCALE: NONE

В 

SCALE: NONE

LENGTH 48" OR AS REQUIRED WHERE DEVICE HEIGHT IS INDICATED

-1/2" DIAMETER STAINLESS STEEL BOLTS WITH LOCK WASHERS, LENGTH AS REQUIRED FOR MOUNTING ON STEEL STRUCTURE. FOR CONCRETE USE 6" LONG EXPANSION (EXISTING) OR ANCHOR (NEW) BOLTS. (TYPICAL FOR 4)

ALUMINUM BASE PLATE



HANDRAIL MOUNTED RECEPTACLE

SCALE: NONE

## NOTES:

- 1. POWER SUPPLY TO MAGNETIC METER PRIMARY DEVICE & TRANSMITTER TO BE FROM SAME SOURCE WITH RESPECT TO VOLTAGE, FREQUENCY AND PHASE
- 2. INSTALLATION OF METERS SHALL PROVIDE STRAIGHT RUNS WITHOUT FITTINGS OF 5 PIPE DIAMETERS UPSTREAM AND 3 PIPE DIAMETER DOWNSTREAM OF METER, WHERE POSSIBLE.





- EXOTHERMIC WELD

MAGNETIC FLOWMETER INSTALLATION

SCALE: NONE

	INTEGRATED Science & Brigineering 1039 Sulivan Road, Suite 200, Newnan, Georgia 30265 (p)678.552.2106 (p)678.552.2107 Atlanta/Savannah COA #: PEF000625 Exp. 6/30/202									
	No.38080 PROFESSIONAL PLOMCINEEB									
		-			-	-		-	ite Apr.	
-	8	7	6	5	4	3	2	1	Rev. Description	
-	Date:Drawn by:Check by:TBDAPDMZProject #:Design by:Review by:1521.2201DMZDLO									
		CONSTRUCTION FLANS	FOR		SYLVANIA WPCP UPGRADES				LOCATED IN LAND LOT ??? OF THE 1ST DISTRICT, SCREVEN COUNTY, GEORGIA	
	ELECTRIC DETAILS 2									
	DRAWING NO. E114									



ESAD, LLC 885 WOODSTOCK ROAD SUITE 430-231 ROSWELL, GA 30075 PH: 678-469-5196